


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas.

HOLLOW- CARTER OIL COMPANY.
 Schmidt No. 5.

SEC. 17 T. 22 R. 3 W.
 NE SE NW

Total Depth. 3502
 Comm. 3-21-34 Comp. 5-28-34
 Shot or Treated.
 Contractor.
 Issued. 6-30-34. Rotary to 3449

County. Harvey



CASING RECORD.

12 1/2" 282' 7" 3449'

Elevation.

Production. Potential 360 B.

Figures Indicate Bottom of Formations

surface	282	lime	3275
shale and shells	555	chat	3282
shale	820	lime	3350
sdv lime and shale	843	shale	3448
shale	1020	sand	3451
lime	1030	cored 3430-45 Full Recovery.	
shale and shells	1095	Cored 3445-51 Full Recovery.	
lime	1110	3451 equals 3449	
shale and lime	1300	lime	3482
shale and shells	1344	shale	3485
shale	1390	Filled 650' oil in 3 hours.	
lime	1465	Swabbed 4 bbls oil per hour.	
shale and shells	1540	1000 gal acid.	
lime	1576	Swabbed 7 bbls oil per hour.	
shale and shells	1884	shale	3502
shale	1934	shot 5 qts 5-11-34 TD	
broken lime	1975	Shot 10 qts 5-11-34.	
shale and lime	2000	Swabbed 1 bbls oil per hour.	
lime	2010	shot 20 qts 5-14-34.	
broken shale	2114	swabbed 2 bbls oil per hour.	
broken shale and lime	2170	2000 gal acid.	
lime	2224	3500 gal acid.	
shale	2244	Potential test. 360 bbls oil 24 hours.	
lime	2260		
shale	2300		
lime	2321		
shale	2375		
sdv lime	2466		
lime	2605		
lime and shale	2712		
shale	2754		
lime	2760		
shale	2770		
lime	2837		
shale	2860		
lime	2865		
shale	2870		
lime	2901		
shale and lime	2915		
lime	3020		
lime and shale	3052		
shale	3160		
chat	3220		
lime	3252		
chat	3268		

RUS