

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BLDG BLDG, WICHITA, KANSAS

Location. NWc SW

Sec. 17 T. 22 R. 3W.

340' NL 330' WL SW $\frac{1}{2}$


Casing Record.

County. Harvey

10" Farm. J.F. Schmidt
 20" 8 $\frac{1}{2}$ " Company. Shell Petroleum Corp.
 15 $\frac{1}{2}$ " 6 5/8" 3436 Contr.
 12 $\frac{1}{2}$ " 280 5 3/16" Comm. 3-28-33

No. 2

Comp. 4-28-33



Total Depth. 3449 $\frac{1}{2}$ Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 5-20-33

Swab 268 bbls in 4 hrs.

Formation	Depth	Formation	Depth.
surface	60	shale	3163
sand	180	chat Top of chat	3163
shale	240	chat	3270
shell	245	shat and lime	3290
shale	250	lime	3353
down for water 12 hours.		shale Top Kinderhook	3353
lime shells	260	Deflection Surveys at 2000'	2500, 3000' OK
shale and shells	300	shale	3438
Reamed 11" hole to 17" to 228		lime Top of Hunton	3438
down for water		Cored 3439-43 Rec 4'	
shale and shells	455	Saturated 3440-42 SLM at 3443	
Reamed 11" hole to 292		Started bailing mud at 6 PM.	
lime	740	bailed to 2600	
lime and shale	825	bailed and put on master gate. Loaded	
lime	925	hole drilled plugs and bailed.	
Acid bottles at 500 and 750 O.K.		lime hard	3444
shale	940	lime hard smell oil	3448 $\frac{1}{2}$
lime	1035	lime soft	3449 $\frac{1}{2}$ TD
shale	1105	Pay filled up 2850' in 1 hr. end 8 AM.	
lime	1130	Swabbed 1096 bbls in 15 hrs. end 12:30	
shale	1360	AM 4-29-33	
down for water.		Swab 609 bbls in 10 hours.	
shale	1450	Swab 268 bbls in 4 hours.	
shale	1650		
shale	1795		
lime	1920		
Acid bottles at 1000', 1250'			
and 1500' O.K.			
lime and shale	1995		
lime	2275		
shale	2370		
lime	2495		
lime shells and shale	2545		
lime	2620		
lime	2910		
lime and shale	2965		
2965 equals 3000 S.L.M. Correction.			
shale and shells	3060		
shale	3110		