


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. S¹/₄ NW DEEPENING RECORD. Sec. 17 T. 22 R. 3W
 2130 S of NL. 330' E of W.L. NW¹/₂ County. Harvey
 Casing Record. 10" Farm. Schmidt No. 1
 20" 8" Company. Skelly Oil Co. and Selby
 15¹/₂" 65/8" Contr.
 12¹/₂" 53/16" Comm. 3-26-33 Comp. 5-10-33
 Total Depth. 3495 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.



Figures Indicate Bottom of Formations.
 Date Issued. 7-28-34

Initial Production.
 1st 24 hours 795 bbls Swabbed.

Formation	Depth	Formation	Depth.
sd ^y shale	300	S.L.M.C 3427 equals 3428	
shale and sand	625	Dark brown Misner sand trace of	
shale and shells	905	shale and lime	3430
shale and sand	965	Grey crystalline lime little sand	3434
shale lime shells	1630	no show. Top of Hunton	3431
shale	1830	Grey crystalline lime and brown dolomite	
lime broken	2000	20% sand	3438
shale sand	2120	soft from 3436-38	
broken lime and shale	2200	1st oil 3436 30' oil in hole and gas	
sd ^y lime	2260	est. 3,000' in 30 min.	
shale and lime	2380	grey lime and sand and brown	
sd ^y shale and lime shells	2450	dolomite	3443
sd ^y lime	2495	hole filled with oil to 2500' in	
lime	2660	first hour and gas Est 100,000 cu ft.	
shale	2680	Well flowed 2 small heads during the	
broken lime	2750	drilling of this footage estimated at	
lime	2790	about 5 B. each.	
lime and shale	2885		
lime	2900	lime and sand soft brown	3452.
broken lime	2915	formation washing free oil, oil rose 2600'	
shale and lime	2980	in hole.	
Var. col shale	3025	lime brownish grey and sand with	
shale and lime	3080	med trace of shale	3455
Var. colored shale Top chat	3143	Washing free oil,	
chat and shale	3153	TD.	3455
chat brown grey med soft	3158		
no show.		24 hrs 102 ¹ / ₂ bbls in chat.	
light brown and grey med sft chat	3163	1st 24 hours Hunton 795 bbls in swab.	
no show			
brown and grey med chat no show	3173		
light brown and grey chat	3178		
small show gas no oil			
grey light and little brown chat hd	3188		
chat grey and trace brown chat hd	3201		
chat and lime	3272		
chat 15% lime 85%	3280		
chat 10% lime 90%	3296		
lime	3320		
lime	3343		
Base of Miss lime	3332.		
Top of Kinderhook Dol	3332		
shale and lime	3369		
shale and shells	3392		
shale and lime	3425		
sand Misner	3427		

DEEPENING RECORD.

Old T.D. 3455
 Comm. 6-13-34 Comp. 6-25-34.
 Prod. Prod. before 260 B.
 After 340 B.
 1500 Gal acid.
 soft coarse dark grey dolomite
 shale 3461
 soft coarse dark grey dolomite
 shale with little pieces brown
 lime 3477
 no saturation.
 grey dolomite, little shale and
 lime med hard 3482
 Grey dolomite, little chert med
 hard 3487
 Grey and brown dolomite med
 hard 3495 T.D.