

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. SE NE SE

Sec. 19 T. 22 R. 3W

990 NL 330' EL SE  $\frac{1}{4}$

Casing Record.

County. Harvey.

10" Farm. P. B. Martens  
 20" 8" 3194 Company. J. E. Mabee-Shell  
 15" 280 65/8" Contr. J. E. Mabee.  
 12" 53/16" Comm. 11-2-32

No. 2

Comp. 11-28-32



Total Depth 3225 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation. 1439

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 12-31-32

flowed 199 bbls in 30 Min with  
 est 3 Million gas.

Formation	Depth
clay	50
sand and shale	280
shale and shells	720
lime	920
shale and shells	1410
shale and shells	1725
lime	1855
lime and shale	1885
lime	1975
shale and lime	2215
shale and lime	2410
lime	2450
lime and shale	3192
top of chat 3192	
chat	3200
Top of chat corrected to	3190
chat hard	3220
chat soft.	3225
flowing. flow est. 100 bbls per hr with 2 to 3 million gas.	
TD.	3225

open for one hour flowing thru  $1\frac{1}{2}$   
 shaeffer flow beam 200# on the well and  
 80 # on the trap. Flow 327 bbls and  
 estimated 4 to 5 million gas. open  
 one half hour with the flow beam  
 by passed. carrying 45#  
 on the trap and 50# on the well  
 flowed 199 bbls in 30 min with est.  
 3 million gas.

3192  
 1439  
 1753