

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. NE SE SW


Sec. 19 T. 22 R. 3W.

Casing Record.

DEEPENING RECORD.

County. Harvey.

10" Farm. Ediger No. 3
 20" 8 1/4" 3135 Company. Sinclair-Prairie Oil Co.
 15 1/2" 65/8" Contr.
 12 1/2" 304 53/16" Comm. 7-26-33 Comp. 9-27-33
 Total Depth. 3544. Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.



Figures Indicate Bottom of Formations.

Date Issued. 10-13-34

Elevation.

Initial Production.

Pumped 936 B. oil in 18 hrs.
 then flowed 50 B. PHR. for 3 Hrs.

Rotary.

Formation	Depth	Top Misner	3324
surface	65	Top Hunton	3327
sand	250	Base Hunton	3357
shale and broken lime	304	Pay	3350-54
shale and shells	1650	Flow 120 bbls 1st 4 hours.	
shale	1750	Flow 210 bbls next 2 1/2 hours.	
shale and shells	2090	Flow 765 bbls in 10 hours.	
shale and shells	2360	Est 100 bbls per hr flow.	
lime	2420	Swabbed 50 bbls per hr.	
shale and shells	2490		
lime	2560	Swabbed 525 bbls 18 hours. 9-15-33	
shale and shells	2645	Swab 760 bbls 16 hours 9-16-33	
lime	2805	Started to flow on 9-17-33	
sand	2845	no test.	
shale and shells	2870		
shale and lime shells	2910		
lime	2945	DEEPENING RECORD.	
shale and lime shells	3035	Old T.D.	3365
shale and shells	3085	Comm. 7-18-34 Comp. 8-22-34.	
shale	3125	Prod. Pot. 607 B.	
Top Chat 3125		shale 3365-	3460
chat	3202	shale	3466
lime	3222	lime	3489
lime brown	3238	shale green	3491
100,000 Gas 3175.		sand	3541
Base Miss Lime 3238.		TD. Top Viola	3466.
shale	3320	154' 5" liner	3466
lime	3321	Bartlesville	3489
3321 equals 3307 S.L.M.		Top Wilcox	3491.
shale	3324	show oil	
sand	3325	T.D. 3535.	
shale blk	3327	600' oil in hole.	
lime	3329	shot 30 qts. 3502-32 Swab 30 B. 20H.	
lime	3357	Swab 78 bbls 12 hours.	
shale	3358	Pump 65" 4 hours.	
shale	3365		
TD.			