

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG WICHITA, KANSAS

Location, SE SW SE

Sec. 19 T. 22 R. 3W

Casing Record.

County, Harvey

No. 4

10" Farm, Martins
20" 8" Company/ Skelly Oil Co.

15 1/2" 65/8" 3525 1/2

Contr.

12 1/2" 445 53/16"

Comma. 7-16-33


Comp. 8-16-33

Total Depth, 3569

Shot

Quarts Between.

Correspondence Regarding This Well Should Be Referred To.



Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued, 9-30-33

520 B. in 23 Hrs.

Formation	Depth	Formation	Depth.
cellar	8	chat	3215
clay	18	chat hard	3262
sand	175	shale	3265
lime bed and clay	300	lime	3300
shale lime	441	lime and shale	3323
lime	445	shale	3345
broken lime	548	broken lime and shale	3373
lime and shale	699	shale and lime shells	3393
lime	708	Misener shale and lime	3401
shale and shells	740	Top of Misner 3393	
broken lime and shale	930	Lime Hunton	3429
lime	972	Top of Hunton 3401.	
red rock	999	Bottom Hunton 3429	
lime	1030	shale lime hard	3465
shale lime shells	1109	shale grey Sylvan	3509
shale shells	1200	shale	3522
shale	1530	lime and shale	3525
lime	1534	lime Viola white hard	3531
shale grey	1550	lime Viola	3537
lime	1556	lime brown and trace of sand	3547
shale	1571	sdv lime and trace green shale	3550
shale hard	1580	sdv lime grey brown	3555
shale sticky blue	1620	lime grey and green shale	3560
shale shells	1695	Wilcox sand grey	3565
broken lime	1792	S.L.M. 3534	
lime	1864	Top of Simpson, 3558	
shale	1871	Top of Wilcox 3559	
lime	1897		
broken lime	1920	8-15-33 Hole filled up 200' oil in 30 Min.	
slate shells	1974	Wilcox sand 3569 T.D.	
broken lime	2080		
lime	2133	8-16-33 Hole filled up 1500' oil in	
broken lime	2150	2 hours.	
shale shells	2240		
broken lime	2290		
sdv lime	2316		
sdv shale	2375		
shale	2440		
lime	2448		
lime short shale breaks	2480		
lime K.C.	2567		
shale sharp	2572		
lime	2684		
broken lime	2710		
lime	2727		
lime sharp	2732		
lime	2916		
lime and shale	2920		
broken lime and shale	2967		
broken lime	2990		
shale	3075		
shale yellow lime shells	3140		
lime	3141		
S.L.M. C. 3075 equals 3069			
shale yellow	3151		