

DRILLING WELL COMPLETION REPORT

Well No. 5 Farm Name J. G. Smisor

Date completed Jan. 3, 1950

Description SW/4 Sec. 30-22S-9W

County Reno State Kansas

Initial production 5 bbls. Total depth 3717 feet

Initial volume _____ cu. ft. _____ lbs. rock pressure

M.C.P.C. Interest 100%

Remarks: _____

A. E. Pierce

W

Mr. McDowell
Accounting Dept.
✓ Scouting Dept.
Geological Dept.
Pipe Line Dept.
Materials Dept.
Rental Dept.
Legal Dept.
Mr. Leo Meyer
Engineering Dept.
Lease Inventory
Income Tax Dept.
File

Mid-Continent Petroleum Corporation
J. C. Smisor Well No. 5
NE SE SW Section 30 - 22 - 9
Reno County, Kansas

Casing: 10 3/4" 269' w/200 sks cement
7" 3672' w/200 sks cement

Perforated: 3673' to 3680' w/48 holes

Commenced: 11-21-49
Completed: 1- 3-50
Initial Production: 5 b. p. d.


<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Surface sand; clay	0	20
fresh water sand	20	24
clay	24	80
Fresh water sand	80	90
sand; clay	90	205
red bed	205	230
red bed; shells	230	545
Red shale	545	705
red shale; shells	705	920
shale; shells	920	1185
shale; lime	1185	2790
lime	2790	2830
lime; shale	2830	2860
lime	2860	2910
lime; shale	2910	2925
lime	2925	3010
lime; shale	3010	3075
shale; lime; shells	3075	3194
lime	3194	3300
lime; chert	3300	3320
lime	3320	3430
lime; shale	3430	3495
lime; chert	3495	3535
shale; shells	3535	3580
shale; lime	3580	3664
shale	3664	3673
broken lime; shale	3673	3675
lime	3675	3677
lime; - hard	3677	3700
lime	3700	3708
sandy lime	3708	3713
lime	3713	3715
Hard Lime	3715	3717 Total Depth.

LOCATION NOTICE

TULSA, OKLA., Nov. 21, 1949

WELL NO. 5 ON J. C. Smisor FARM

WILL BE AS FOLLOWS:



FEET FROM NORTH LINE
 330
 FEET FROM EAST LINE
 990
 FEET FROM SOUTH LINE
 FEET FROM WEST LINE

IN SW/4 SEC. 30 TWP. 22S RANGE 9W

Reno COUNTY, STATE OF Kansas

REMARKS: R. L. Mankey - Dist. Supt.

A. E. Johnson - Foreman

M. C. P. C. — 100%

SIGNED A. E. Pierce

W

COPIES TO

MR. McDOWELL
 DISTRICT SUPT.
 ACCOUNTING DEPT.
 SCOUTING DEPT. ✓
 GEOLOGICAL DEPT. •
 PIPE LINE DEPT.
 MATERIALS DEPT.
 RENTAL DEPT.
 LEGAL DEPT.
 INCOME TAX DEPT.
 MR. LEO MEYER
 ENGINEERING DEPT.
 LEASE INVENTORY
 CLAIM DEPT.
 MR. J. W. BASORE
 FILE

9 Card for