

Computer Inventoried



Natural Gas • Crude Oil
Exploration & Production

COPY

McCOY PETROLEUM CORPORATION

110 South Main, Suite 500
Wichita, Kansas 67202

316-265-9697

John Roger McCoy
President

Kevin McCoy
Vice-President

Harvey H. McCoy
Vice-President

Keith McCoy
Treasurer

McCoy Petroleum Corporation
Greathouse "A" #1-8
NE NE SE Section 8-22S-32W
Finney County, Kansas

RELEASED

NOV 18 1993

FROM CONFIDENTIAL

OCT 2
CONFIDENTIAL

Page 2 ACO-1

DST #1 4748-4770' w/straddle packers.
Packer failure.

DST #2 4714-4770' w/straddle packers.
Open 30", S.I. 60", Open 60", S.I. 90"
Weak blow, increase to 3-1/2" blow on 1st open.
Weak blow, increase to 1-1/4" blow on 2nd open.
Recovered 120' of mud. No show of oil or gas.
FP 78-89# 89-100#
ISIP 973# FSIP 939#

ELECTRIC LOG TOPS

Winfield	2674 (+ 228)
Heebner	3888 (- 986)
Toronto	3904 (-1002)
Lansing	3930 (-1028)
Stark	4280 (-1378)
Hushpuckney	4326 (-1426)
Marmaton	4438 (-1536)
Fort Scott	4538 (-1636)
Cherokee	4555 (-1653)
Morrow Shale	4718 (-1816)
1st Morrow Sand	4736 (-1834)
2nd Morrow Sand	4749 (-1847)
St. Genevieve	4756 (-1854)
St. Louis	4820 (-1918)
LTD	5004 (-2102)