

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

API No. 15 — 055 — 20,089
County Number

S. 6 T. 22 R. 33 W

Loc. C SE SE

County Finney

Operator

I. Wayne Woolsey

Address

514 Petroleum Building, Wichita, Kansas 67202

Well No.

2-A

Lease Name

Stevenson

Footage Location

660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

I. Wayne Woolsey

Spud Date

3-16-72

Total Depth

4785

P.B.T.D.


Date Completed

4-28-72

Oil Purchaser

The Permian Corporation

640 Acres
N



Locate well correctly

Elev.: Gr. 2894

DF 2896 KB 2899

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		10-3/4"		404		250	
Production		7"		4784	50-50 Pozmix	130	collapsed
Production		4-1/2"		4388		50	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	D.P. Jet	4728-36

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	4715	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 Gal. mud acid; 2000 gal. 28% Acid	4728-36

INITIAL PRODUCTION

Date of first production 5-3-72		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 90 bbls.	Gas MCF	Water trace bbls.	Gas-oil ratio -- CFPB	
Disposition of gas (vented, used on lease or sold) used on Lease			Producing interval(s) 4728-36		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator I. Wayne Woolsey DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 2-A Lease Name Stevenson Oil

S 6 T 22 R 33 W

WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
No tests or cores			Chase	2530
			Heebner	3778
			Lansing	3796
			Marmaton	4320
			Cherokee	4414
			Morrow	4621
			Ste. Genevieve	4667
			St. Louis	4726
			Total Depth	4785

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



I. Wayne Woolsey Signature

Title

Date