

CONTRACTOR'S WELL LOG

JUN 8 0 REC'D
State Geological Survey
WICHITA BRANCH

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

The Maurice L. Brown Company
Abercrombie Drilling, Inc.
STEVENSON "A" #4
C SE, Section 6-22S-33W,
Finney County, Kansas
5-1-80
5-20-80

SPUD DATE:
COMPLETION DATE:

0	223	Surface sand & Shale
223	610	Shale & Sand
610	2301	Sand & Shale
2301	2340	Shale & Red Bed
2340	2505	Sand & Shale
2505	2775	Lime & Shale
2775	2975	Sand & Shale
2975	4282	Shale & Lime
4282	4332	Lime & Shale
4332	4368	Lime
4368	4590	Lime & Shale
4590	4680	Lime
4680	4723	Lime & Shale
4723	4738	Lime
4738	4740	Lime & Shale
4740	4800	Lime
	4800	Rotary Total Depth

Spud hole at 11:30 a.m., 5-1-80. Drilled 610' of 12 $\frac{1}{4}$ " hole. Ran 15 joints of 8-5/8" - 23# new casing. (Tally 597.11) Set at 601.36'. Cemented with 300 sacks of HLC, $\frac{1}{4}$ # gilsonite per sack, 3% Ca.Cl., followed with 150 sacks of Class H, 3% Ca.Cl. Cement by Halliburton. Cement did circ. Plug was down at 3:30 a.m., 5-2-80.

T.D. 4802'. Ran 121 joints of 5 $\frac{1}{2}$ " - 14# casing. (Tally 4770'). Set at 4765'. Cemented with 150 sacks of HLC, followed with 100 sacks of posmix. Plug was down at 7:00 p.m., 5-20-80.

SAMPLE TOPS:

Anhydrite 2005'
B/Anhydrite 2019'

STATE OF KANSAS)

) SS