

KANSAS DRILLERS LOG


Geological Survey
WICHITA, BRANCH

S. 6 T. 22 R. 33 E W

API No. 15 — 055 — 20,071
County Number

Loc. C NE NE

County Finney

640 Acres
N

Locate well correctly

Elev.: Gr. 2895

DF KB 2902

Operator I. Wayne Woolsey		
Address 514 Petroleum Building, Wichita, Kansas 67202		
Well No. #1	Lease Name Stevenson	
Footage Location 660 feet from (N) line 660 feet from (E) line		
Principal Contractor Earl Wakefield, Inc.	Geologist George N. Mueller	
Spud Date 12-31-71	Total Depth 4780	P.B.T.D.
Date Completed 3-21-72	Oil Purchaser The Permian Corporation	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"		401	Common	150	3% cc
Production	7-7/8"	5-1/2"		4779	Pozmix	100	2% Gel 18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	D.P. Jet Shots	4719-4724
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8"	4743	4743			



ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 Gal. 15% SME Acid	4719-4724
2000 Gal. 28% Acid	4719-4724

INITIAL PRODUCTION

Date of first production 3-21-72		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 100 bbls.	Gas MCF	Water 2% bbls.	Gas-oil ratio not measured CFPB	
Disposition of gas (vented, used on lease or sold) used on Lease			Producing interval (s) 4719-4724		


INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator I. Wayne Woolsey		Designate type of comp.: OIL, GAS, DRY HOLE, SWDW, ETC.:		
Well No. 1	Lease Name Stevenson	Oil		
S <u>6</u> T <u>22</u> R <u>33</u> ^W				
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 (Marmaton) Limestone, white to Light brown, finely xln. porosity Rec. 15' oil specked mud FP 9-18#, SIP 1038-983# 30"-30"-15"-30"	4316	4335	Chase Heebner Lansing Marmaton	2522 3775 3821 4312
DST #2 (Cherokee) 30"-30"-15"-30" Rec. 68' mud, FP 37-92# SIP 426-185# Lms. tan to bugg, trace vuggy porosity, slight spotted stain	4404	4431	Cherokee	4404
DST #3 (Morrow) 30"-30"-30"-30" Rec. 15' mud, FP 18-18#, SIP 64-46#. Gray fine grain sandstone, VSSO.	4620	4645	Morrow	4609
DST #4 (St. Louis) 30"-30"-30"-60" Rec. 235' gas, 126' gassy clean oil, 62' sli mud-cut gassy oil, 62' hvy mud-cut oil, 63' sli oil-cut mud; FP 83-176# SIP 1240-1203# Lms. lt gray, Co oolitic, Gd inter-oolitic por. Gd show free oil.	4715	4742	St. Louis	4730
			Total Depth	4780
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
		 Signature		
		Title		
		8-24-73 Date		

SEP 15 1972 SE: STEVENSON #1 LOCATION: C NE NE
 OWNER: T. W. & ADA S. EASON, PARTNERSHIP SECTION 6-22S-33W
 CONT: EARL F. WAKEFIELD, INC. FINNEY CO., KANSAS
 COMM: 12-31-71 CASING: 8 5/8" SET @ 410' 1504
 COMP: 1-15-72 IP: P 100 BOPD & 2% Wtr/ST Louis 5 1/2" SET @ 4779' 1004
 GR 31

Elevation: None

Surface Clay, Sand, Blue Clay	322
Blue Clay	416
Shale	1235
Shale & Anhydrite	1680
Shale	2432
Shale & Lime	2680
Lime & Shale	2875
Lime	4780
R.T.D.	4780



NO TOPS

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) ss.

I, GORDON L. KOELLING, DO HEREBY CERTIFY THAT THIS IS A TRUE
 AND CORRECT LOG ON THE STEVENSON #1, LOCATED C NE NE OF SECTION
 6-22S-33W, FINNEY COUNTY, KANSAS.

EARL F. WAKEFIELD, INC.

BY Gordon L. Koelling
 Gordon L. Koelling

Read and sworn to before me this 21st Day of January, 1972.

Notary Commission Expires:
October 22, 1972

Carol Jean Noel
 Carol Jean Noel - Notary Public

