


SEP 15 1972

6-22-33W  
C NW SE

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG



STEVENSON #3A  
C NW SE, Section 6-22S-33W  
Finney County, Kansas

API-15-055-20,093

Elevation: NONE  
IP: P 20 BOPD & 20% Wtr./MISS

Commenced: March 28, 1972  
Completed: April 10, 1972

OPERATOR: T. W. EASON & ADA S. EASON - Partnership

Depth		Formation	Remarks
From	To		
0	261	Sand, clay, shale	Ran 20 jts used 28# 8 5/8" csg. set @ 418' cemented w/100 sks Howcolite w/2% CC @ 150 sks common w/3% C.C. P.D. @ 8:30 AM 3/29/72 Cement Cir.  Ran 149 jts of used 5 1/2" csg. set @ 4796' cemented w/100 sks 50-50 Posmix 12 1/2# Gilsonite per sack - 18% salt w/12 bbl. Preflush ahead of Plug. P.D. @ 6:10 PM 4/10/72
261	870	Shale	
870	1489	Shale, sand	
1489	1527	Anhydrite	
1527	1885	Sand, shale	
1885	2505	Shale	
2505	2670	shale, lime stks	
2670	3118	Lime, shale	
3118	3235	Shale, lime	
3235	3530	Lime, shale	
3530	3700	Lime	
3700	2870	Lime w/shale	
3870	4045	Lime, shale	
4045	4264	Lime	
4264	4332	Lime, shale	
4332	4800	Lime	
4800	TD		

NO TOPS

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in Section 6-22S-33W, Finney County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
James S. Sutton, II

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 12th day of April, 1972, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.