

A-10-81
MAP NO. K-52

ELEV. 2878 DF

STATE Kansas COUNTY Finney SEC. 32 Twp 22S Rge 33W

OPERATOR Champlin Oil & Ref. Co. LOC. SE SE SE

WELL NO. 1 FARM NAME Esther G. Vernon FT. FROM _____ LINE

COL Unnamed (PD 4875) FT. FROM _____ LINE

FR. 9-14-61 SPUD 9-10-61 COMP. 9-27-61

CONT./GEOL. Lonita Oil Corp., Inc. Tools

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a					
b					
c					
d					

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

b " " " " " "

c " " " " " "

d

D & A D & A (X)

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 4861

CASING - CEMENT RECORD

SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.

8-5/8" 386 275

OPERATOR Champlin Oil & Refg. WELL NO. #1 Esther G. Vernon ELEV. 2878 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Topeka	3710		Heebner	3808	
Heebner	3802		Toronto	3827	
Toronto	3826		Lansing Kansas City	3859	
B/Kansas City	4359		B/Kansas City	4350	
Marmaton	4376		Marmaton	4376	
Cherokee	4491		Cherokee	4492	
			Morrow	4690	
			Morrow Sand	4720-40	
			Ste Genevieve	4743	
			St Louis	4761	

Spud 9-10-61. 8-5/8" @ 386 w/275 sx.
 DST #1 (Morrow) 4690-4740, op 2 hrs, Rc 15' M, ISIP 870/30 mins,
 FP 40-45, FSIP 185/60 mins.
 TD 4860, (St. L), log 4861.
 DST #2 (Morr & Miss) 4690-4861, op 2 hrs, Rc 60' M w/50, ISIP
 800/30 mins, FP 55-80, FSIP 635/60 mins.

D & A 9-27-61
COMPLETE.

LIBERAL ELECTRIC LOG TOPS

2881 KB

Winfield 2583 (+300)

Heebner 3808 (-927)

Toronto 3837 (-956)

Lansing 3858 (-977)

Marmaton 4374 (-1493)

Morrow 4690 (-1809)

"S₂" Sand 4720 (-1839) 14/20; tst Mud

Ste. Gen 4743 (-1862) tst Mud

St. Louis 4798 (-1917)

TD 4860

D & A

44