

A-9-242 2874 KB  
 MAP NO. K-52 ELEV. 2869 GL  
 STATE Kansas COUNTY Finney SEC. 33 Twp 22 S Rge 33W  
 OPERATOR Lonita Oil Corporation, Inc. - Wichita LOC. SW SW SW  
 WELL NO. 1 FARM NAME Damme FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 POOL Wildcat (PD 4850) FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 FR. 7-24-61 SPUD. 7-24-61 COMP. 9-22-61

CONT./GEOL. Company tools Jim Ralston/Geol

NAME PRODUCING INTERVAL COMPLETION RECORD  
 FROM — TO PERF. W/HOLES TREATMENT RECORD  
 a Morrow 4734-50 64 None

b \_\_\_\_\_  
 c \_\_\_\_\_  
 d \_\_\_\_\_

a I. P. OIL/DIST. P/377 BG WTR. \_\_\_\_\_ GAS \_\_\_\_\_ M.C.F.P.D. \_\_\_\_\_ CHK. P HRS. 24

b " " " " " "

c " " " " " "

d \_\_\_\_\_

D & A ( )

SIP# \_\_\_\_\_ FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_

GOR. \_\_\_\_\_ GR. 32° PBTD \_\_\_\_\_ TD 4877

| SIZE   | DEPTH | CASING - CEMENT RECORD<br>W/SAX. SIZE | DEPTH | W/SAX. |
|--------|-------|---------------------------------------|-------|--------|
| 8-5/8" | 365   | 275                                   |       |        |
| 5 1/2" | 4872  | 525                                   |       |        |

OPERATOR Lonita Oil Corp WELL NO. 1 Damme ELEV. 2874 KB

| SAMPLE TOPS      | DEPTH | SUB SEA | ELEC. TOPS       | DEPTH   | SUB SEA |
|------------------|-------|---------|------------------|---------|---------|
| Heebner          | 3783  |         | Heebner          | 3795    |         |
| Lansing          | 3824  |         | Kansas City      | 3846    |         |
| Base Kansas City | 4315  |         | Base Kansas City | 4340    |         |
| Marmaton         | 4336  |         | Marmaton         | 4370    |         |
| Cherokee         | 4464  |         | Cherokee         | 4482    |         |
|                  |       |         | Unconformity     | 4682    |         |
|                  |       |         | Morrow Sand      | 4736-51 |         |
|                  |       |         | Mississippian    | 4760    |         |
|                  |       |         | St Louis         | 4779    |         |

Spud 7-24-61. 8-5/8" @ 365 w/275 sx.

DST # 1 (Chero) 4675-95, op 1 hr, wk blo/6 mins, rec 30' Mud, pressure 0/30 mins.

DST # 2 (Morrow) 4733-77, op 1 hr, rec 100' Mud + 2930' oil (gty 35°), FP 620-1310, SIP 1415/20 mins.

DST # 3 (Morrow) 4779-4805, op 1 hr, rec 90' SOCM, FP 0-60, SIP 1295/20 mins.

TD 4872, logs to 4877. 5 1/2" @ 4872 w/225 sx.

DV @ 2690 w/300 sx. MICT.

P 64/4734-50. Swb 15 BOPH/4 hrs, no treatment. POP.

IP P/377 BOPD, gty 32° from Morrow 4734-50. 9/22/61

LIBERAL LOG TOPS

2874 KB

Winfield 2576 (+298)

Heebner 3794 (-920)

Lansing 3844 (-970)

Marmaton 4356 (-1482)

Morrow 4682 (-1808)

"S-2" 4734 (-1860) 15/15; \$ 15 BOPH; ¢ P 377 BOPD

Ste. Gen 4753 (-1879)

TD 4872