

MAP NO. 1-17-61 ELEV. 2885 DF
 STATE Kansas COUNTY Finney SEC. 27 Twp 22S Rge 33W
 OPERATOR Champlin Oil & Refg. Co. LOC. C NW SW
 WELL NO. 3 FARM NAME Edward R. Adams FT. FROM _____ LINE _____
 OL. Damme (PD 4800) FT. FROM _____ LINE _____
 FR. 11-29-60 SPUD 11-25-60 COMP. 1-13-61

CONT./GEOL. Garvey Drlg. Tools Buddy Sprage-Geol.

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>St. Louis</u>	<u>4785-69</u>	<u>33</u>	<u>8250 Ac</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d _____	_____	_____	_____

d I. P. OIL/DIST. P/135 BORD GAS _____ M.C.F.P.D. _____ CHK. P HRS. 24
 b " " " " " "
 c " " " " " "
 d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. 30.5° PBD 4771 TD 4802
 CASING - CEMENT RECORD

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>9 5/8"</u>	<u>361</u>	<u>250</u>	_____	_____	_____
<u>5 1/2"</u>	<u>4801</u>	<u>200</u>	_____	_____	_____

OPERATOR Champlin Oil & Refg. Co. WELL NO. #3 Edward R. Adams ELEV. 2885 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	3796		Lansing	3836	
Toronto	3810		Marmaton	4333	
Base Kansas City	4310		Morrow	4633	-1748
Lansing	3840		Ste. Genevieve	4667	
Marmaton	4335		St. Louis	4731	
Cherokee	4451				
St. Louis	4715				

Spud 11-25-60, 9 5/8" @ 361 w/250 sx.
 DST #1 (Lansing) 4050-73, op 2 hrs, Rc 70' mud, ISIP 1160/60 mins, FP 20-60, FSIP 1050/60 mins.
 DST #2 (Marmaton) 4417-52, op 2 hrs, Rc 600' HGC&VHOCM, ISIP 750, FP 100-200, FSIP 750/30 mins.
 DST #3 (Mississippian) 4695-4753, op 2 hrs, Rc 2' mud, All Press "0".
 RTD 4800, Logs to 4802.
 DST #4 (St. Louis) 4750-4802, op 2 hrs, Rc 330' HO&GCM, FP 90-120, FSIP 655/60 mins.
 5 1/2" @ 4801 w/200 sx., CO to 4771
 P/33/4758-68, 750 MA + 7500 Ac, Swb 1 1/2 BO/7 mins, Swb 14 BOPH/2 hrs.

POP. pmp 118 BO + 1% wtr/24 hrs.
IP 135 BOPD, no wtr, Gty 30.5°, Calc from 8 hr test,
from St. Louis (4758-68).

LIBERAL ELECTRIC LOG TOPS

2887 K.B.

Winfield 2580 (+307)

Heebner 3796 (-909)

Lansing 3835 (-948) tst Mud

Marmaton 4326 (-1439) DST rec 600' HGC&VHOCM

Morrow 4624 (-1737) No Sand

St. Gen 4672 (-1785) tst Mud

St. Louis 4736 (-1849) IPP = 135 BOPD

RTD 4802