


5-42W MAP NO. 52 ✓ SEC. 29-22S-33W
 STATE Kans COUNTY Finney LOC SE NE SE
 OPER. Texaco Inc., Wichita, Kansas FT/FR _____ LINE _____
 WELL 1 FARM R.L. Becker FT/FR _____ LINE _____
 OOL Damme ELEV. 2889 GR. 2899 OF 2901 KB
 INT. Garvey Drlg. GEOL. Jim Allison
 CO. INT. 4800' Oil Test
 F.R. 3-25-63 SPUD. 3-22-63 COMP. 5-7-63
 TD. 4830 FM. Mississippian PBD. _____
 COMP. RECORD Miss 4730-84 - 36 - 6650A
Co P 46 BOPD + 34 BWPD (Gr 29 deg)
8 5/8" @387/265 sx. 4 1/2" @4825/190 sx.



Data Inc.

(KB Log)

Hb	3804	- 903	Chero	4490	-1589
Lans	3860	- 959	Morr	4664	-1763
KC	3956	-1055	Miss	4724	-1823
Pleas	4339	-1438	LTD	4826	-1925
Marm	4364	-1463	RTD	4830	-1929

4776-84
4730-40

Ø #1 (KC) 4156-75½, R 19½' total=10' ool lm w/ sli fluor + 5' chalky ool lm + 4½ tight cem ool & xln lm

DST #1 (Marm) 4440-63, Op 1 hr, R 235' MSW, ISIP 115#/NT, IFP

90#, FFP 144#, FSIP 1079#/NT

DST #2 (Morr) 4706-28, Op ½ hr, No Blow, flush tool, pkr fail

Ø #2 (Miss) 4765-76, R 9' total=3' hard lm + 2' shly lm + 1' ch + 2' frac'ed lm + 2; shly lm + 1½' ch + ½' por lm w/SO

Ø #3 (Miss) 4776-4804, R 28' total=9' pot lm w/SO + 6' tite lm + 13' vert frac'ed lm w/NSO, RTD 4830, 4½" 4825/190 sx., MICT

CO 4794, Correl Log 4150-4794, 16/4776-84 (Miss), \$ perf ld, \$

7 GMSW w/ NSO or G/4 hrs, 250A, \$ dn, \$ 8 BO + 19 BAW & SW/

8 hrs, FU 4 BO + 2 BW/12 hrs, \$ 6 BO + 4 BSW/10 hrs, 3000 gell

A (15%) + 100 reg A, \$ 80 BLW & AW/NT, \$ 21 BO + 32 BAW/10 hrs

w/sli SG, FU 4 BO + 6 BW/12 hrs, \$ 13 BO + 19 BSW/9 hrs, 20/

4730-40 (Miss), \$ 2 BO + 2½ BSW/1 hr, 300 Reg A (15%) + 3000

gell A (15%) + 1d O + 32 ball sealers in perfs 4730-40, \$ 11 BNO

- 155 BLO + 29 BSW/12 hrs, POP, P 9 BO + 35 BW/12 hrs, P 29 BO

+ 55 BW/24 hrs, P 46 BO + 37 BW/24 hrs, Co P 46 BOPD + 34 BWPD,

Gravity 29 deg., Miss 4730-84, COMPLETED

C80

Win 2586 + 315

Lans 3860 - 959

Mrm 4365 - 1464

Mo 4668 - 1767

Miss 4724 - 1823