

\*

Field Damme

State Kansas County Finney

Company Rocket Drig. Co. NCKA

Farm Clark Well No. 3

Sec. 22 Twp. 22S Range 33W

fr N fr E fr S fr W

of NW SE SW

Contractor \_\_\_\_\_

Remarks PD 4816!

Comm. 6/5/56 Comp. 8/1/56

Elev. 2880 B.I. T. D. 4800 P. B. \_\_\_\_\_

Pay 4693 - 4704 Miss

I. P. pump 91 BOPD R. P. \_\_\_\_\_

Casing Record: 13 3/8 \_\_\_\_\_ 7

20 \_\_\_\_\_ 10 3/4 \_\_\_\_\_ 5 1/2 4800/120

16 \_\_\_\_\_ 8 5/8 263/200

	LOC	Tops	Log
<u>JUN 1 3</u>	<u>43065</u>		<u>Heeb 3766 - 3775</u>
<u>JUN 2 0</u>	<u>44370</u>		<u>Aug 3810 - 3807</u>
	<u>DST 4024 - 4054 op 1 hr. wh</u>		<u>Buc 4291 - X</u>
	<u>bls to sec 390' mud. w</u>		<u>Man 4313 - 4314</u>
	<u>sls - show oil FFP 270 BHP 1860/20</u>		<u>CCK 4434 - 4439</u>
	<u>2120 BHP 1500</u>		<u>Miss 4641 - 4664</u>
	<u>DST 4387 - 4405 op 1 hr wh</u>		<u>2880</u>
<u>M/M</u>	<u>bls to sec 215' fluid (125'</u>		<u>176'</u>
	<u>OCM. 90' sls w 0.9 m.)</u>		<u>4662</u>
	<u>FP 120 BH 1060t/20</u>		<u>1785</u>
	<u>44485</u>		
<u>JUN 2 7</u>	<u>DST 4510-50 op 1 hr. ST-6/6 TO.</u>		
	<u>TEL 2820' mud FP 1220 BHP 2200/20</u>		
	<u>DST 4679 - 4719 - op 1 hr. sec 180' wh.</u>		
	<u>0.9 c.m. BHP 260t</u>		
	<u>DST 4719 - 4734 op 1 hr. sec 90' OCM.</u>		
	<u>BHP 100t.</u>		
	<u>RTD 4800' low log set 5 1/2"</u>		
	<u>4800/120 WOCT</u>		

JUL ✓

JUL 11 MICT Co? # 33/4693-4704 sho oil  
A/1000 13 hrs. fr. avg 1.5 boph.

JUL 18 ~~avg~~ 2604-06 - pop

7/25 pumping Avg 75-80 bbl oil per day.

AUG 1

State potential  
91 BOPD + NO WATER

### AMARILLO TOPS

2880 KB

Winfield 2567 (-313)  
Heebner 3775 (-895)  
Lansing 3818 (-938)  
Marmaton 4314 (-1434)  
Cherokee 4439 (-1559)  
Morrow 4625 (-1745)  
Miss 4664 (-1784) Oil