


State Kansas Field off set.
 Company W. L. Hartman County Finney
 Farm Holsted-Thomason No. 1
 Sec. 25 Twp. 22S Range 33W
 Spot SW SW SW
 Contractor _____
 Remarks _____
 Comm. _____ Comp. 1-22-94
 Elev. DF 2867 GL KB _____ TD 4905 PB _____
 Pay _____



I.P. _____ Press. _____
 Casing Record: 13 3/8 7"
20" 10 3/4 5 1/2" 4670
16" 8 5/8

	Sample	Log
Heeb 3819; Lan 3859; Marm 4350; DST 4378-4410, op 1 hr, rec 175' O&GCM, BHP 1025#; DST 4400-10, op 1 hr, rec 90' oil, BHP 1020#; DST 4435-4460, op 1 hr, rec 110' gas + 150' sli OCM + 60' HOCM + 120' NCOil, BHP 1090#; C 4460-97, full rec; Cher 4488; Patterson ss 4663; C 4665-4700, rec 35'; 4674-77, spdt stn; C 4700-4748, rec 48'; Miss 4704; C 4748-98, rec 46'; 4777-79, ool ls spot por & stn; RTD 4905, perf 18/4598-4604, 24/4577-85 SW + SS0; 24/4585-93; 49/4577-93; 18/4477-83, XW + SS0, sqz; perf 48/4442-58, SO; A/500, swb 4 BO/1 hr, tr wtr; swb 7 BF1PH, 9% wtr/5 hrs; 59 BF1/18 hrs, 5% wtr; G. 27.5°, pump 55 BO/24 hrs + 16% wtr, G. 30.6°; Phyl 232 BO No wtr/24 hrs.		

Mvm

Log Tops
 Anky 1873
 Hol 2512
 Her 2537
 Kri 2560
 Winf 2598 +269

U/Ft. R 2660; L/Ft. R 2720;
 Heeb 3818 Lans 3866 (-999)
 Marm 4374 (-1507) Cher 4488 (-1621)
 Patt ss 4693 (-1826)
 Miss 4703 (-1836)

12/53

to April 1960 Prod. 12, 519 80