

*** OWWO


5

State Kansas Field Finney
 Company D. R. Leuch-Texas Company County Finney
 Farm Graves "B" No. 1
 Sec. 9 Twp. 22 Range 33

Spot SE SE NE

Contractor

Remarks Formerly CSO FO Miss. Test.



Comm. Comp. 8/1/56
 Elev. DF GL KB TD 4911 PB 2409
 Pay 2530-36 2556-70 2580-90

I.P. 5.261 MCF Press. CP 390#
 Casing Record: 13 $\frac{3}{8}$ 7"
 20" 10 $\frac{3}{4}$ 5 $\frac{1}{2}$ " 2715/1000
 16" 8 $\frac{5}{8}$ 240/1190

	Sample	Log
4911 was RTD, CO to 2736		H/H 2529
had 8 5/8" @ 240/1140		W/K 2556
in hole, set 5 $\frac{1}{2}$ " to		L Kri 2579
2715 w/ 1000, CO to 2654,		Win 2612
perf 20/2611-16, A/250		
frac/1000, sd/1000, prep		
to test.		
JUL 18 CO: A/2000 g 117 MCF. PBTD 2600 PB 16/2556-70		
at 40/2580-90 1244 16/2556-70 CO to 2622		
g 5.261 MCF + 450 g wph but g 4.777 + 133		
g wph - PBTD 2609 g 3.038 MCF + 144 g wph		
blowing to dry.		
7/25 g 3.168 + 67 g wph PB to 2548 24/		
2530-36 frac 1000/ sd/1000 CO to 2609 51 2 hrs.		
g 2.350 MCF + 50 g wph. but g 2.264 + 28 g wph.		
ph. testing.		
AUG 1 72/20 g 5.261 MCF		
CP 390#		

[Handwritten signature]

AMARILLO TOPS

2893 KB

Winfield 2610 (~~4~~283)

Heebner 3808 (-915)

Lansing 3850 (-957)

Morrow 4660 (-1767)

"S-2" Sd 4684 (-1791) T 17', 13' por, NT

Miss 4748 (-1855) NS

TD 4911 (-2018)