

A-10-41

MAP NO.

K-52

STATE Kansas COUNTY Finney SEC. 34 Twp 22S Rge 33WOPERATOR W. L. Hartman LOC. NE NE SWWELL NO. 1 FARM NAME Finnup "D" 2800 FT. FROM N LINEPOOL Finnup (PD 4850) 2100 FT. FROM W LINEFR. 6-30-61 SPUD 7-3-61 COMP. 9-27-61 N.C.R.A. FO of SecCONT./GEOL. Lonita Oil Corp.

NAME PRODUCING INTERVAL		COMPLETION RECORD	PERF. W/HOLES	TREATMENT RECORD
FROM	TO			
<u>Mississippian</u>	<u>4767-72</u>		<u>23</u>	<u>5250 Ac</u>
b				
c				
d				

a I. P. OIL/DIST. P/273BQPD GAS M.C.F.P.D. CHK. P HRS. 24

b " " " " " "

c " " " " " "

d

D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. 30.9° PSTD 4824 TD 4878

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
		W/SAX.			
<u>8-5/8"</u>	<u>356</u>	<u>250</u>			
<u>4-1/2"</u>	<u>4875</u>	<u>400</u>			

OPERATOR W. L. Hartman WELL NO. #1 Finnup "D" ELEV. 2879 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
No log tops available					
<u>Heebner</u>	<u>3796</u>				
<u>Lansing</u>	<u>3839</u>				
<u>B/Kansas City</u>	<u>4320</u>				
<u>Marmaton</u>	<u>4346</u>				
<u>Cherokee</u>	<u>4467</u>				
<u>Mississippian</u>	<u>4681</u>				

Spud 7-3-61. 8-5/8" @ 356 w/250 sx.

DST #1 (Marmaton) 4410-65, op 1 hr, Rc 90' M, No FP, FSIP 880/NT.

DST #2 (Cherokee) 4515-45, op 1 hr, Rc 20' M, all press "0".

DST #3 (Mississippian) 4752-90, op 1 hr, Rc 40' HO&GCM, no FP, FSIP 500/NT.

RTD 4878, (Miss), logs. 4-1/2" @ 4875 w/400 sx. MICT. CO to 4824, GR-N logs.

P/3/4770, swb 1 Gal F/30 mins (3/4 Oil).

P/20/4767-72, swb/SSO, 250 MA, Frac w/5000 Ac (no sd). Swb 16 BOPH/12 hrs.

POP

4649
20/02

IP pump 273 BOPD, Gty 30.9° from Mississippian 4767-72.

9/27/61

609504