


A=10-38

MAP NO. K-52

ELEV. 2884 KB

STATE Kansas COUNTY Finney SEC. 16 Twp 22S Rge 33WOPERATOR D. R. Lauck Oil Co., Inc. loc. C SE NWWELL NO. 3 FARM NAME Euwer FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_OOL Damme (PD 4750) FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_FR. 7-3-61 SPUD 6-30-61 COMP. 9-27-61CONT./GEOL. Lauck Drilling Tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM - TO	PERF. W/HOLES	
<u>Patterson</u>	<u>4416-22</u>	<u>24</u>	<u>750 Ac</u>
b			
c			
d			



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	P	HRS.
<u>P/132BOPD</u>	<u>2 1/2 BOPD</u>				<u>P</u>	<u>24</u>
b						
c						
d						

I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	P	HRS.
b						
c						
d						

I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	P	HRS.
b						
c						
d						

I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	P	HRS.
b						
c						
d						

D &amp; A ( )

SIP#	FI TP #	FI CP#	SIBHP
	<u>30.5°</u>	<u>4560</u>	<u>4781</u>
GOR.	GR.	PBTD	TD

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>10-3/4"</u>	<u>195</u>	<u>165</u>				
<u>7"</u>	<u>4769</u>	<u>100</u>				

OPERATOR D.R. Lauck Oil Co., Inc. WELL NO. # 3 Euwer ELEV. 2884 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	3763		Heebner	3763	-879
Lansing	3816		Lansing	3810	
B/Kansas City	4281		B/Kansas City	4282	
Marmaton	4307		Marmaton	4307	-1423
Cherokee	4426		Cherokee	4427	
Patterson	4615		Patterson	4615	-1731
Mississippian	4671		Patterson Sand	4629	
			Mississippian	4671	-1787

Spud 6-30-61. 10-3/4" @ 195 w/165 sx.

DST #1 4385-4431, op. 1 hr, Rc 120' O&GCM / 240' GCM / 60' O&GCM, ISIP 190/20 mins, FP 120-205, FSIP 1115/20 mins.DST #2 (Chero) 4435-87, op 30 mins, wk blo 4 mins, by pass tool, Rc 10' M, ISIP 110/NT, FP 0-0, FSIP 40/NT.DST #3 (Patterson) 4627-67, op 2 hrs, wk blo, Rc 60' M, ISIP 65/30 mins, FP 0-0, FSIP 60/30 mins.

RTD 4781, logs. 7" @ 4769 w/100 / 1200 Gal latex. MICT.

P/20/4668-73, 64/4689-4703, Frac 15,000 Oil X 15,000 sd, swb 18 BO / 98 BW/5 hrs. Set plg @ 4560.

4 P 24/4416-22, A/750, swb 9 BOPH/31 hrs.

POP

IP Pump 132 BO +  $2\frac{1}{2}$  BWP, Gty 30.5° from Marmaton 4416-22.  
9/27/61

LIBERAL ELECTRIC LOG TOPS

2884 KB

Krider 2522 (+362)

Winfield 2570 (+314)

Heebner 3762 (-878)

Toronto 3778 (-894)

Lansing 3808 (-924)

Marmaton 4302 (-1418)

Cherokee 4408 (-1524)  $\phi$  Pu 132 Bopd +  $2\frac{1}{2}$  BW

Morrow 4612 (-1728)

"S-2" Sand 4626 (-1742) 0/12, tst 60' Mud

Miss (Ste. Gen) 4668 (-1784) swb 18 BO + 98 BW/5 hrs

TD 4781