


Company - CARTER OIL CO.
 Farm - Tresmon Miller No. 1.

26-22-34W
 SEC. 26 T. 22 R. 34W
 N E 37

15-055-00126
 County. Finney
 KANSAS



Total Depth. 2830'
 Comm. 6-25-44 Comp. 8-9-44
 Shot or Treated.
 Contractor. Helmerich & Payne, Inc.
 Issued. 12-9-44

CASING:

10 $\frac{5}{8}$ " 543' Cem.
 7" 2608' Cem.

Elevation. _____

Production. 1,190,000 G.

Figures Indicate Bottom of Formations.

sand & shale	365
shale	490
shale & shells	650
sand	730
shale sdy & shells	820
shale & shells	1245
red bed	1305
shale variegated	1385
anhydrite	1406
shale variegated w/anhydrite	1445
shale variegated w/salt & anhydrite	1510
red bed & shale	1875
shale variegated, anhydrite	2000
shale	2012
anhydrite	2035
shale & anhydrite	2080
shale variegated, anhydrite	2215
shale & anhydrite	2555
dolomite & shale	2585
dolomite	2625
lime	2631
lime hd	2638
red bed	2648
red bed, shale gry	2669
lime gry hd	2683
sand med	2690
anhydrite & dolomite	2696
lime hd	2709
lime	2719
lime gry	2733
lime gry hd	2755
lime	2768
lime brwn & shale	2775
lime brkn	2782
sand sharp	2785
lime	2790
red rock	2793
lime brkn	2802
lime hd, sand sharp	2815
lime gry	2820
lime	2830

Log:
 Hallenberg 2525
 Herington 2555
 Krider 2608
 Winfield 2663
 S. Riley 2719
 Ch. L. Hart 2802