

15-055-00325

22-22.34W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 22 T. 22 R. 34W

FARM Werner NO. 1

LOC. NE NE SW

100' S. & 100' W
of Center

TOTAL DEPTH 2705

COMM. 4-7-50


COMP. 4-12-50

SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 5-26-51

COUNTY Finney



CASING

8 5/8" 605 cem w/275 sxs.
5 1/2" 2704 cem w/700 sxs.

ELEVATION 2942

PRODUCTION 1,920,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	60
sand	85
shale	305
shale & shells	435
sand	450
shale & shells	605
shale	1075
red bed	1325
shale & shells	1920
shale	1995
anhydrite	2040
shale & shells	2280
shale & anhydrite	2515
shale & lime	2705
Total depth	

Tops:

Herington	2507
Upper Krider	2534
Lower Krider	2554
Winfield	2584
Upper Ft. Riley	2644

Perforated:

40 shots	2508-16
90 shots	2530-48
50 shots	2554-60
50 shots	2584-90
30 shots	2600-06
20 shots	2636-40
50 shots	2646-54

SIP 423.4#