

MAR 6 1993

CONFIDENTIAL

~~CONFIDENTIAL~~

Barexco Inc.

DRILL STEM TESTS

AP2# 15-055-21047

Ruby Jean #1-34
C SE SW Sec 34-22S-34W
Finney County, KS

COPY

RELEASED

APR 7 1994

FROM CONFIDENTIAL

DST #1 Lansing "D" 3890-3905'
 15(30)60(120)
BLOW: strong
BLOW: strong
IH: 2210
IFP: 72/84
ISIP: 940
FFP: 72/84
FSIP; 940
FH: 2190
T°: 119°F
Rec: 1060' SW (cl 18,000 ppm)

DST #2 Lansing "G" 3990-4001'
 15(30)60(120)
BLOW: weak
BLOW: weak, died in 6 min
IH: 2053
IFP: 31/31
ISIP: 649
FFH: 31/31
FSIP: 819 (building)
FH: 2013
T°: 118°F
Rec: 5' drlg mud w/no show

DST #3 Lansing "H" 4032-46'
 15(30)60(120)
BLOW: strong blow off btm of bucket in 9 min
BLOW: strong blow off btm of bucket in 11 min
IH: 2063
IFP: 31/114
ISIP: 1020
FFP: 197/254
FSIP; 1070
FH: 2003
T°: 122°F
Rec: 120' gas in pipe & 65' CGO (43° gty) & 180' gas wtr & oil cut mud
 (10% oil, 10% gas, 5% wtr, 75% mud) & 425' sulfur wtr. Cl 34,000,
 put 2,800.

34-225-34w

ORIGINAL

CC
MAR 6 1993
CONFIDENTIAL

DRILL STEM TESTS

Ruby Jean #1-34
C SE SW Sec 34-22S-34W
Finney County, KS

~~CONFIDENTIAL~~

DST #4 Maramton 4294-4309'
15(30)60(120)
BLOW: weak blow
BLOW: no blow
IH: 2078
IFP: 10/10
ISIP: 799
FFP: 20/20
FSIP: 809
FH: 2066
T°: 123°F
Rec: 10' drlg mud

RELEASED

APR 7 1994

FROM CONFIDENTIAL

DST #5 Pawnee 4326-48'
15(30)60(120)
BLOW: very weak blow
BLOW: very weak blow
IH: 2143
IFP: 31/31
ISIP: 1010
FFP: 41/41
FSIP: 1070
FH: 2123
T°: 123°F
Rec: 10' OCM (20% gas, 10% oil, 70% mud)

DST #6 4358-90' packer failure. NO TEST

DST #7 Pawnee 4348-4380'
15(30)60(120)
BLOW: very weak surface blow
BLOW: very weak blow, died 23 min
IH: 2023
IFP: 41/41
ISIP: 1120
FFP: 52/52
FSIP: 1100
FH: 2013
T°: 124°F
Rec: 10' drlg mud w/no show

ORIGINAL

DRILL STEM TESTS

Ruby Jean #1-34
C SE SW Sec 34-22S-34W
Finney County, KS

COPY
CONFIDENTIAL
KCC

MAR 6 1993

CONFIDENTIAL

RELEASED

APR 7 1994

FROM CONFIDENTIAL

DST #8 Ft. Scott 4392-4420'
 15(30)60(120)
BLOW: fair blow throughout
BLOW: fair, increasing to strong in 10 min. Stayed strong for remainder of
 period.
IH: 2184
IFP: 86/86
ISIP: 1070
FFP: 102/108
FSIP: 1203 (building)
FH: 2030'
T°: 120°F
Rec: 900' gas in pipe & 5' clean oil & 95' gas & oil cut mud (5% oil, 70%
 gas, 25% mud) no wtr. Oil gty 32° @ 58°F.

DST #9 St. Louis 4742-4768'
 15(30)60(120)
BLOW: strong, off btm of mucket in 1 min
BLOW: strong blow immediately, again off btm of bucket in 1 min
IH: 2329
IFP: 151/205
ISIP: 1029
FFP: 259/345
FSIP: 1060
FH: 2246
T°: 127°F
Rec: 3000' gas in pipe & 1080' clean gassy oil. Gty 27° @ 64°F.