



Natural Gas • Crude Oil
Exploration & Production

McCOY PETROLEUM CORPORATION

110 South Main, Suite 500
Wichita, Kansas 67202
316-265-9697

15-22-34W

John Roger McCoy
President

Kevin McCoy
Vice-President

Harvey H. McCoy
Vice-President

Keith McCoy
Treasurer

CONFIDENTIAL
RECEIVED
APR 7 1991
FROM [unclear] CONFIDENTIAL

McCoy Petroleum Corporation
#1-15 Cook "E"
C NW NW Section 15-22S-34W
Wildct
Finney County, Kansas

Page 2 (ACO-1)

DST #1 4378-4395' (Marmaton "B")
Open 30", S.I. 60", Open 60", S.I. 90"
Strong blow in 14 minutes on 1st open period.
Strong blow in 16 minutes on 2nd open period.
Recovered 315' of gas in pipe,
30' of clean gassy oil,
285' of muddy water,
360' of salt water (75,000 ppm).
FP 61-185# 291-328#
ISIP 924# FSIP 851#/30" (clock stopped)

DST #2 4470-4500 (Ft. Scott)
Open 30", S.I. 60", Open 60", S.I. 90"
Weak to strong blow in 4 minutes on 1st open period.
Strong blow in 5 minutes on 2nd open period.
Recovered 2160' gas in pipe,
690' clean gassy oil,
120' slightly mud cut oil,
90' gassy oil cut mud,
FP 79-140# 169-264#
ISIP 1107# FSIP 1097#

ELECTRIC LOG TOPS

Winfield	2610 (+347)
Council Grove	2820 (+137)
Heebner	3818 (-861)
Lansing	3875 (-918)
Stark Shale	Absent
Marmaton "B"	4381 (-1424)
Pawnee	4456 (-1499)
Ft. Scott	4480 (-1523)
Cherokee Sh.	4496 (-1539)
Morrow Sh.	4708 (-1751)
St. Louis	4814 (-1857)
RTD	5003 (-2046)

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1991

REGISTRATION DIVISION
Wichita, Kansas