

90037

3-333 51
 MAP NO. 51 SEC. 20 TWP. 22S RGE. 34W
 STATE Kans COUNTY Finney LOC. C SE NW
 OPERATOR Horizon Oil & Gas Co. FT. FROM LINE
 WELL NO. 1- 20 FARM NAME Burg FT. FROM LINE
 POOL Amazon Ditch ELEV. 2972 GR 2981 DF 2982 KB
 2/1/62 SPUD 2/4/62 COMP. 4/3/62
 CONT. Prime Drlg Rig #3. /GEOL.


NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
		FROM - TO	PERF. W/HOLES		
a	Marm	4286-92	12	500 A	
b					
c					
d	Co P				

d I. P. OIL/DIST. 120 BO WTR. NW GAS M.C.F.P.D. CHK. HRS. 24

b " " " " " "

c " " " " " "

d



PERMANENT FILE COPY

SIP# FI TP # FI CPH SIBHP
 GOR. GR. 38.1 deg PBD 4325 TD 4860
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
 8 5/8" 570
 4 1/2" 4855

OPERATOR Hoizon Oil & Gas Co. WELL NO. 1-20 Burg ELEV. 2982 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB
KB Tops & Datuma					
			Winf	2542	- 440
			Hb	3744	- 762
			Tor	3760	- 778
RTD (St Lou)	4860	-1878	Lans	3801	- 819
			Marm	4267	-1285
			Morr	4599	-1617
			St Gen	4645	-1663
			St Lou	4742	-1760
			LTD (St L)	Not avail.	

RTD 4860. Log. No DST's. 4 1/2" @ 4855 w/160 sx. 46/
 4725-48 (St Gen) Scum Oil, PB ? 36/4687-4704 (St Gen)
 Swb no sho, PB ?, 16/4648-45 (St Gen) Swb no sho PB
 Est 4325 PBD, 12/4286-92 (Marm) 500 A, Swb 10 BOPH.
 POP. State Pot: (8 Hr Pmp Rate) Cal P 120 BOPD/NW,
 Grav 38.1 deg. Marm 4286-92.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2982 KB

Winfield 2538 (+444)
Heebner 3744 (-762)
Toronto 3760 (-778)
Lansing 3800 (-818)
Marmaton 4262 (-1280) \$ 10 BOPH
Morrow 4598 (-1616)
Ste. Gen 4682 (-1700) \$ NS
St. Louis 4744 (-1762) \$ scum oil
TD 4860