

90025
2486 KB

A-7-135

MAP NO. 51

STATE Kansas COUNTY Finney SEC. 20

ELEV. 2983 DF, 2975 GL
Twp 22S Rge 34W

OPERATOR Horizon Oil & Gas Co.

LOC. C NW SW

WELL NO. 1 FARM NAME Barrett

FT. FROM _____ LINE _____

DOJ. Geol. WC (Hugoton) (PD 5400) Amazon Ditch FT. FROM _____ LINE _____

FR. 5-11-61 SPUD 5-9-61 COMP. 6-19-61

CONT./GEOL. Holm Drilling Tools (Tulsa)

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
St Louis 4768-74 24 3,000 Ac

b _____

c _____

d _____

d I. P. OIL/DIST. P/336 BQPD GAS _____ M.C.F.P.D. _____ CHK. P HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 4900

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>556</u>	<u>350</u>			
<u>4-1/2"</u>	<u>4865</u>	<u>225</u>			

OPERATOR Horizon Oil & Gas Co. WELL NO. #1 Barrett

ELEV. 2983 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Chase	2702	
			B/Heebner	3752	
			Marmaton	4258	-1275
			Cherokee	4413	
			Morrow	4624	-1641
			Ste Genevieve	4678	-1695
			St Louis	4728	-1745
			Spergen	4854	

Spud 5-9-61. 8-5/8" @ 556 w/350 sx.

DST #1 (Lansing) 3880-3923, op 1 hr, tr gas to surf, Rc 150' MSW / 1460' SW/SO, ISIP 1000/30 mins, FP 110-800, No FSIP.

DST #2 (Marmaton) 4357-82, op 1 hr, gd blo TO, Rc 50' MSW / 400' SW, ISIP 1220/30 mins, FP 30-220, FSIP 1190/30 mins.

RTD 4900, logs (I-ES, IND, Sonic & Cal).

DST #3 (St Louis) 4748-80 (SP), op 65 mins, Rc 1900' GIP / 30' O&GCM / 180' SGCO / 90' M&SGCO / 60' HGCO / 30' SG&OCM, ISIP 1245/30 mins, FP 80-180, FSIP 1185/30 mins.

4-1/2" @ 4865 w/225 sx. Top cem 3400. Frontier-Isotion log to 4828.

P 24/St. Louis/4768-74, swb dry/SO, 500-15% MA, swb ld + 130 BO/
NT, 2500-15% Ac + 2500 wtr, swb ld + 300 BNO/25 hrs. tbg @
4720.

POP

IP P 336 BOPD (no wtr) no Gty or GOR available
from St. Louis 4768-74.

LIBERAL ELECTRIC LOG TOPS

2986 KB

Winfield 2554 (+432)

Heebner 3742 (-756)

Toronto 3768 (-782)

Lansing 3804 (-818) tst XW tr gas

Marmaton 4290 (-1304) tst XW

Morrow 4624 (-1638)

Ste. Gen 4679 (-1693)

St. Louis 4761 (-1775) ϕ Pu 336 BOPD, No wtr

TD 4900