

State Geological Survey  
WICHITA BRANCH

15-093-20393


KANSAS DRILLERS LOG

S. 4 T. 22 R. 35 <sup>R</sup> W

Loc. NW SW NE

County Kearny

640 Acres  
N



Locate well correctly

Elev.: Gr. 3116

DF 3118 KB 3121

API No. 15 — 093 — 20,393  
County Number

Operator  
J. A. Allison, et al

Address  
200 West Douglas, Suite 748 Wichita, Kansas 67202

Well No. #2 Lease Name Rooney "B"

Footage Location  
1640 feet from (N) line 330 feet from (E) (W) line

Principal Contractor DNB Drilling, Inc. Geologist Robert E. McCann

Spud Date March 15, 1977 Total Depth 4585 P.B.T.D. 4512

Date Completed Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½	8 5/8		265	Common	250	2% Gel 3% cc
Production		5½		4583	Common	150	60-40 Poz mix

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP'S	4449-4451
					4458-4460

TUBING RECORD

Size	Setting depth	Packer set at
2"	4469	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid 500 Gal. MCA,	4449-4451
2000 Gal. NE	4458-4460

INITIAL PRODUCTION

Date of first production March 25, 1977	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls. Gas MCF Water + bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **J. A. Allison** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **2** Lease Name **Rooney "B"** Oil

S **4** ~~22~~S **R35**W <sup>E</sup><sub>W</sub>

**WELL LOG**


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - op 30, si 30, op 60, si 45, Weak blow-1st opening Weak intermittent-2nd opening, rec. 35 mud w/few specks oil, IBHP 1146, FBHP 1146, IFP 49, FFP 49	4376	4434	ELECTRIC LOGSTØØBS Heebner Toronto Lansing BKC Marmaton	3862 3881 3912 4376 4399
DST #2 - op 30, si 30, op 30, si 30, Weak blow-died in 20' rec. 5' drlg mud, IBHP 724, FBHP 540, IFP 16, FFP 16	4491	4524	Beymer Zone Johnson Zone Cherokee Shale Log TD	4492 4521 4542 4567
DST #3 - op 30, si 45, op 60, si 60, Weak imit blow-imer. to good, rec. 335 muddy water w/few spots of oil IBHP 836, FBHP 819, IFP 65, FFP 229	4518	4550		
DST #4 - Straddle packers-op 30, si 45, op 90, si 60, Fair imit blow-imer. to good, rec. 684 gas in the pipe, + 84 heav. oil & gas cut mud, + 64 gas cut oil, IBHP 1150, FBHP 1118, IFP 32, FFP 95	4445	4475		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_

  
 J. A. Allison Signature  
 Operator Title  
 July 7, 1977 Date

DRILLERS' LOG

4-22-35W

J. A. ALLISON  
Rooney B-2  
NW SW NE, Sec. 4-22S-35W  
Kearny County, Kansas

Elev: 3121 K.B.  
3116 Gr.

Commenced: 3/15/77  
Completed: 3/25/77

Surface Casing: 265'  
of 8-5/8" used casing, cemented  
w/250 sx common, 2% gal, 3%cc  
3/15/77

<u>FORMATION</u>	<u>DEPTH</u>	
Surface Hole	0	- 235
Sand & Lime	235	- 264
Shale & Shells	264	- 1065
Shale	1065	- 2254
Shale, Sand & Lime	2254	- 2640
Shale	2640	- 2865
Lime & Shale & Sand Strks	2865	- 3100
Lime	3100	- 3300
Shale & Lime	3300	- 3364
Lime & Shale	3364	- 3985
Kansas City	3985	- 4110
Shale	4110	- 4255
Lime & Shale	4255	- 4434
Lime	4434	- 4524
Lime & Shale	4524	- 4550
Lime	4550	- 4585 R.T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 28th day of March, 1977.

*Ella Priess*

Ella Priess, Notary Public

