


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 20 T. 22S R. 35W E

Loc. C SW NE

County Kearny

640 Acres
N



Locate well correctly

Elev.: Gr. 3080

DF 3082 KB 3085

API No. 15 — 093 — 20569
County Number

Operator
J.A. Allison

Address
300 W. Douglas Suite 305 Wichita, Ks. 67202

Well No. # 2 Lease Name Rooney "C"

Footage Location
1980 feet from (N) ~~XXXX~~ 1980 feet from (E) ~~XXXX~~

Principal Contractor DNB Drilling, Inc. Geologist Robert J. Gill

Spud Date November 4, 1978 Total Depth 4882 P.B.T.D.

Date Completed November 15, 1978 Oil Purchaser Permian Oil

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8"		285'	Common	200	2% Gel, 3% CC
Prod.		5-1/2"		4605'		200	60/40 Poz, 10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP	4496-4500

Size	Setting depth	Packer set at
2-1/2"	4538'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
860 Gals. MSR Acid (Dowell)	4496-4500
2000 Gals. 15% HCL NE Acid (Dowell)	4496-4500

INITIAL PRODUCTION

Date of first production December 27, 1978	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) 4496-4500

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

J. A. ALLISON

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil

Well No.

2

Lease Name

ROONEY "C"

S 20 T 22 R 34 EX W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p><u>DST #1</u> op 30, si 30; op 60, si 45, strong blow, rec. 60' mud, 1365' SW, IF 65, FF 655, ISIP 1098, FSIP 1098;</p> <p><u>DST #2</u> op 30, si 30; op 60, si 45, good blow, rec. 100; gas, 290' oil, 180' muddy oil, IF 68, FF 188, ISIP 1078, FSIP 958, Temp. 109°.</p> <p><u>DST #3</u> op 30, si 30, very weak blow, rec. 5' mud, IF 32, ISIP 0, Temp. 106°.</p>	4447	4490	<u>ELECTRIC LOG TOPS:</u>	
			Heebner	3904 (- 819)
			Lansing	3957 (- 872)
			Base Kans.C.	4326 (-1241)
			Marmaton	4354 (-1269)
			Beymer	4442 (-1357)
			Johnson	4476 (-1391)
			Cherokee	4490 (-1405)
			Morrow	4724 (-1639)
			Eroded Miss.	4822 (-1737)
	4575	4605	Mississippi	4852 (-1767)
			El. Log TD	4881 (-1796)
			RTD	4882 (-1797)
(Dresser Atlas Laterolog)				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. A. Allison
J. A. Allison

Signature

Owner

Title

February 6, 1979

Date

DRILLER'S LOG

J. A. ALLISON
No. 2 Rooney 'C'
C SW NE Sec. 20-22S-35W
Kearny Co., Ks.

Commenced: 11-3-78
Completed: 11-15-78

Surface Casing: 277' of 8-5/8"
cmtd w/200 sx common, 2% gel,
3% cc. 10-3-78

FORMATION

DEPTH

Surface Hole	0 - 285
Shale	285 - 676
Sand & Shale	676 - 1859
Shale	1859 - 2150
Sand & Shale	2150 - 2406
Shale	2406 - 3610
Shale & Lime	3610 - 3805
Lime & Shale	3805 - 3935
Lime	3935 - 4051
Lime & Shale	4051 - 4460
Lime	4460 - 4494
Lime & Shale	4494 - 4527
Lime	4527 - 4882 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 15th day of November, 1978.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

