

SAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 _____ County _____ Number _____

Operator
J. A. ALLISON

Address
300 W. Douglas, Suite 305, Wichita, Ks. 67202

Well No. 3 Lease Name ROONEY "C"

Footage Location
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor DNB Drilling Co. Geologist Robert J. Gill


Spud Date 4/15/80 Date Completed 4/24/80 Total Depth 4897 P.B.T.D. 4592

Directional Deviation _____ Oil and/or Gas Purchaser _____

SEP 8 1980
State Geological Survey
WICHITA BRANCH

S. 20 T. 22 R. 35 W

Loc. C SE NE
County KEARNY



Elev.: Gr. 3092

DF _____ KB 3103

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12-3/4	8-5/8"	20#	289	common	275	3% cc 2% gel.
Oil String	7-7/8	5-1/2	14#	4890	60/40 Poz	150	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			8		4820-4824
TUBING RECORD			8		4490-4496
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Ac 500 MCA, Tested Dry	4820-4824
Ac 2500 Gals. 15% HCL NE	4490-4496

INITIAL PRODUCTION

Date of first production 6/27/80	Producing method (flowing, pumping, gas lift, etc.) Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 45 bbls.	Gas MCF	Water 45 bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 4490-4496		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

J. A. ALLISON

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil

Well No.

3

Lease Name

ROONEY "C"

S 20 T 22 R 35 ~~W~~

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

DST #1, op 30, si 45; op 60, si 45, rec 60' o & gcm, 510' oil, 380' oil & gas cut saltwater - total fluid 950 zone 15', thick, ISIP 590, FSIP 573, IF 163 FF 344

4483

4510

ELECTRIC LOG TOPS

Heeb	3815- 712
Tor	3833- 703
Lans	3872- 769
BKC	4350-1247
Marm	4377-1274
Beymer	4456-1352
John	4484-1381
Cher	4516-1413
Mrw	4757-1654
Miss	4875-1772

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. A. ALLISON

Signature

Operator

8/29/80

Title

Date

15-093-20687
20-22-35W

State Geological Survey
WICHITA, BRANCH

DRILLER'S LOG

J. A. ALLISON
Rooney 'C' No. 3
C SE NE
Sec. 20-22S-35W
Kearny Co., Ks.

Commenced: 4-15-80
Completed: 4-24-80

Surface Casing: 279' of 8-5/8"
cemented w/275 sx common, 3% cc
4-15-80

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 289
Sand & Shale	289 - 1295
Shale	1295 - 2565
Shale & Lime	2565 - 2822
Shale	2822 - 3300
Lime & Shale	3300 - 3735
Lime	3735 - 3880
Lime & Shale	3880 - 4230
Lime	4230 - 4375
Lime & Shale	4375 - 4439
Lime	4439 - 4510
Lime & Shale	4510 - 4600
Lime	4600 - 4690
Lime & Shale	4690 - 4865
Lime	4865 - 4897 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.
Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 29th day of April, 1980.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas