

36-22-35W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WARREN PETROLEUM CO.

SEC. 36 T. 22 R. 35W

LOC. NE NE SW

330' loc.

FARM Landon

NO. 1

TOTAL DEPTH 2660

COMM. 7-6-49

COMP. 8-5-49


SHOT OR TREATED

CONTRACTOR Burris Drilling Co.

ISSUED 1-6-51

COUNTY Kearny

KANSAS



CASING

10" 349' cem. w/250 sx.

7" 2518' cem. w/100 sx.

ELEVATION

3001 (m)

2998

2995 2nd.

PRODUCTION 11,878,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	10
sand & gravel	210
sand	300
clay yllw	310
shale	650
sand	670
lime	715
shale	915
red rock	1145
anhyd.	1195
red rock & shale	1680
red rock, shale, anhyd.	1885
red rock	1990
anhyd.	2065
shale & lime	2205
lime & anhyd.	2220
red rock & shale	2260
lime & shale	2300
anhyd., lime	2470
lime	2550
shale	2574
lime sdy	2610
shale & shells	2624
lime	2635
shale	2640
lime sdy	2660
Total Depth	

Tops:

Anhyd.	1932
Stone Corral Dol.	1990-2004
Herrington-Krider	2516-52
Winfield	2570-2606
Upper Fort Riley	2634-60

Cable 2520-2660