

90094

5-180W Map No. LS-51 REPL COMP

OPER ROBERT E. CAMPBELL
Wichita, Kansas
#1 FOSTER
Wakefield Drilling
FIELD Hugoton
P. 4 Pt Cal OF; Ga 80,000 CFGPD, SIP 325#,
Kri 2594-2652



S-T-R 31-22S-35W
SPOT App NE SW SW
CO KEARNY, Ks.
ELEV 3162 KB

(KB Logs:)
Herr 2592 f 570
U/Kri 2614 f 548
L/Kri 2624 f 538
Winf 2676 f 486
LTD NA
RTD 2685 f 477
DDTD 2712 f 450

RTD 2685, No Log, 7" @2685' w/450 Sx., DD 2693, NSG, DD
2712 in Winf, NSG in Winf OH, PB 2675, Pf 40/2642-52 & 16/
2540 44 & 16/2594-98 (Kri) 500 (3%) Acid & Frac 20,000 gal
wtr x 20,000 sd, Flo 4 BLWPH & gas (no Ga) 4 Pt Cal OF Ga
80,000 CFGPD, SIP 325#, Kri 2594-2652 - Completed (5-19-65)
REPLACEMENT COMPLETION for 9-30 65

Replaced with correct spot: - Was 31-23S-35W- Is 31-22S-35W
Also U/Kri was 2614 f 518 - Is 2614 f 548 - Corrected

Data Inc

MISCELL DATA
GEOL Woody Paul LS ELEV 3160 DF SPUD DATE 12-24-64
FTG 3154 GR DRLG COMP _____
SUPPT _____ FR by DATA 12-23-64
CSG 10" @262' w/260 Sx. 7" @2685' w/450 Sx. COMP by " 5-19-65