


31-22-37W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CLYDE BEYMER, JR & GRAHAM-MICHAELIS DRLG. SEC. 31 T. 28 R. 37W
Farm- Modie No. 2 C SE $\frac{1}{4}$

Total Depth. 2631'
Comm. 7-23-57 Comp. 7-28-57
Shot or Treated.
Contractor. Graham-Michaelis Drlg. Co.
Issued. 9-28-57

County Kearny
KANSAS



Elevation. 3309'

Production. 2,000,000 CFG

CASING:

8 5/8" 305' w/150 sx cem.
5 1/2" 2564' w/100 sx cem.

Figures indicate Bottom of Formations.

surface sand-rock-gyp	397
shale	850
red bed	1205
lime-chalk, shale-gyp	2111
lime-shale	2495
shale-shells-chalk-lime-	
anhydrite	2570 RTD
Drilled to	2631
Total Depth	

TOPS:

Herrington	2553
Krider (scout)	2565
Winfield	2595

Show of gas natural @ 2604'
amounting to 60 MCF
Fractured w/10,000 acid frac &
10,000 lbs. sand. Well gauged 1,200
MCF after 8 hrs. Test on 72 hr.
shut in, 20 min. blow down was
2,000 MCF.