

25-22S-38W ORIGINAL

RELEASED

NOV 15

JAN 21 1994

CONFIDENTIAL

CONFIDENTIAL

FROM CONFIDENTIAL

DRILL STEM TESTS

Luella #1-25
SE NW Sec 25-22S-38W
Kearny County, KS

DST #1 Upper Morrow Sand 4707-4758
15(30)60(120)
BLOW: strong throughout
BLOW: strong w/gas to surface, TSTM in 48 minutes.
IH: 2482
IFP: 148/189
ISIP: 239
FFP: 223/239
FSIP: 247
FH: 2200
T°: 119°F
Rec: 345' clean oil (55% gas, 40% oil, 5% mud), & 245' OCM (5% oil).
Gravity 39° @ 80°F.

DST #2 Morrow 4760-4822
15(30)60(120)
BLOW: strong blow off stm of bucket in 2 min - died 15 min.
BLOW: no blow during final flow period.
IH: 2369
IFP: 156/280
ISIP: 280
FFP: 280/280
FSIP: 280
FH: 2259
T°: 119°F
Rec: 530' muddy SW w/specks of oil. RW 22 @ 72°F (cl 32,000) pit 3300' cl.

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1991

CONSERVATION DIVISION
Wichita, Kansas