

PLUGGING PROCEDURE
RECEIVED

MYRA BELL # 1-3

CSW/4NE/4 SECTION 3-T22S-R39W
HAMILTON COUNTY, KANSAS
API# 075-20579

OCT 15 2001
KCC WICHITA

SURFACE CASING:	8 5/8" 24# J55 STC @ 473'	KB: 3450'
PRODUCTION CASING:	4 1/2" 10.50# K55 ST&C @ 5410'	GL: 3439'
TUBING:	160 JTS. 2 3/8" 6.5# J55 EUE @ 5045'	
RODS:	100 x 5/8" & 100 x 3/4" & 24' Pony Rods	
PERFORATED INTERVAL:	MORROW 4994'-5008'	
PBTD:	CIBP @ 5150'	
CEMENT:	5410'-4500' (265 SKS) 3261'-2050' (675 SKS) (DV TOOL @ 3261') 1150'-11' (260 SKS) (PRODUCTION CASING) 488' - 11' (255 SKS) (SURFACE CASING)	

PROCEDURE

1. NOTIFY KANSAS CORPORATION COMMISSION PRIOR TO COMMENCEMENT OF PLUGGING OPERATIONS. FILE PLUGGING APPLICATION FORM (CP-1) PRIOR TO START OF PROCEDURES. (620) 225-8888 (DODGE CITY OFFICE)
2. MIRU WELL SERVICE UNIT. LAY DOWN & WAREHOUSE RODS & PUMP.
3. RELEASE TUBING ANCHOR, TOOH AND LAY DOWN 160 JTS. 2 3/8" TUBING, PERFORATED SUB, AND MUD ANCHOR. TRUCK TO STORAGE LOCATION OR SELL ON-SITE.
4. RD & RELEASE WELL SERVICE UNIT.
5. MOVE IN CEMENTERS, RU TO CASING, ESTABLISH PUMP RATE, PUMP 40 SKS CEMENT FOLLOWED BY 200# HULLS, GEL SPACER TO 3261', THEN CEMENT VOLUME TO COVER CASING FROM DV TOOL TO SURFACE (3261'- SURFACE).
6. DIG OUT SURFACE CASING AND CASING HEAD, PUMP 50 SKS. FOR SURFACE CAP IF NEEDED.
7. CUT OFF CASING AND WELLHEAD 4' BELOW GROUND LEVEL.
8. REMOVE SURFACE EQUIPMENT AND RESTORE LOCATION.