


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

FRANK HOLLOW ET AL.
D.B. Bartel No. 2

SEC 36 T. 22 R. 4W.
SE SW SE

Total Depth. 3347
Comm. 6-27-36 Comp. 8-15-36
Shot or Treated.
Contractor. The McPherson Drilling Co.
Issued. 12-5-36

County. Reno.



CASING.

12 $\frac{1}{2}$ " 297' 7" 3271'

Elevation. 1451

Production. Pot. 217 B.

Figures Indicate Bottom of Formations.

sand and clay	230	lime	3009
broken lime	297	shale	3164
broken lime	1070	shale Var. col.	3180
lime	1086	lime broken	3188
shale and red rock	1118	shale	3280
shale	1270	chatt soft	3288
broken lime	1292	chatt hard	3295
shale and shells	1650	chatt hard	3325
broken lime	1736	chatt soft	3345
shale	1814	oil at 3335	
broken lime	1925	show of gas at 3295	
shale	1958	Total Depth after driving wool plug	
lime	1964		3342 $\frac{1}{2}$
broken lime	2041	plug drilled out total Depth	3347
shale	2130		
broken lime	2146		
lime	2207		
broken lime	2380		
sd lime	2408		
shale	2535		
broken lime	2540		
shale	2570		
lime	2650		
sd lime	2690		
Porous lime	2717		
lime	2783		
shale	2804		
lime	2882		
Porous lime	2890		
lime	2969		
shale	2973		

3253
1451

1802