

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union Nat. Bldg., Wichita, Kansas.


W.C.MCBRIDE, INC.,
 Siemens No. 1.

SEC. 36 T. 22S R. 4W
 SW SE SE

Total Depth. 3350'
 Comm. 5-17-36 Comp. 6-15-36.
 Shot or Treated. 2000 Gals. Acid,
 Contractor. Olson Drlg. Co.
 Issued. 7-13-36

County. Reno

CASING: Rotary O-3262'
 15 1/2" 302' Cable 3262-3350
 8 5/8" 3264'



Elevation. 1453

Production. Pot. 903 B.

Figures Indicate Bottom of Formations.

sand & clay	210	broken brown & lime white	2720
red rock	225	lime hard	2765
salt	280	lime	2819
sand & lime	302	lime hard	2823
lime & shale hard	311	lime soft	2838
shale & shells	399	limo	2863
brkn shale & salt	410	lime hard	2890
shale & shells	520	shale	2901
brkn lime & shale	662	lime	2930
lime brokon	750	lime hard	2945
shale & shells	782	lime grey hard	2963
br oken lime	797	sticky shale	2988
shale & shells	862	broken lime & shale	3022
soft broken lime	918	lime	3050
shale & shells	998	shale	3062
shale & lime shells	1195	broken lime	3079
limo broken	1259	broken lime & shale	3084
broken lime hard	1309	lime broken	3090
shale & shells	1312	shale & shells	3114
shale	1552	broken lime & shale	3165
shale & lime shells	1717	shale & lime shells	3191
shale & shells	1890	shale & shells	3205
broken lime & shale	1955	variegated shale	3236
shale sticky	1993	lime & shale	3253
limo & shale breaks	2069	chat (3262=3266 S.L.M.)	3262
lime	2175	reduced hole at 3268'	
broken lime & shale	2195	lime	3350
lime	2251	Total Depth	
shale	2267		
lime hard	2292	Small show of gas	3268-3293
shale & shells	2329	Small show of oil & inc in gas	3325-31
sand & shale	2344	110' oil in hole in 7 hrs.	3331-3334
sandy shale	2365	275' oil in hole	3334-3336
broken lime & shale	2394	500' oil in hole	3336-3342
sdylime	2422	1000' oil in hole-500' oil increase	
lime	2432	in 45 minutes.	3342-3350
lime broken	2460		
shale & lime shells	2554	6-19-36 24 hr test before acid	288 Bbls.
lime	2656	6-23-36 24 hr test after acid	903 Bbls.
broken limo	2678		
lime hard	2693	Mississippi Lime (Chat)	3257-3350

3257
 1453
 -1804