

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Union Nat'l Bk Bldg., Wichita, Kansas.


W. C. MC BRIDE, INC.
Abraham Dick No. 1

SEC. 36 T. 22 R. 4 W.
SE SW SW

Total Depth 3397'
Comm. 8-3-35 Comp. 9-7-35
Shot or Treated.
Contractor Lloyd, Frost & Stuy.
Issued. 9-28-35

County- Reno

Rotary 0 to 3273
CASING. cable tools 3273-3397'



15 1/2" 278 8 5/8" 3273
13 3/8" 602

Elevation 1453

Production Dry.

Figures Indicate Bottom of Formations.

clay sand & shale	278
shale	521
salt shale & shells	730
shale	912
shale & shells	990
lime	1005
brkn lime	1130
shale & shells	1370
shale	1505
shale & shells	1643
shale	1940
lime	2350
shale	2420
lime	2642
lime with shale breaks	2673
lime	2910
shale & lime shells	2945
shale	2988
shale & lime shells	3067
shale	3107
shale & lime shells	3132
shale	3255
shale & lime	3262
chat	3278
lime	3322
chat	3370
sand hard & white	3377
sdv lime	3388
lime	3397

Very small show oil 3295-3300.

Shot gas & oil 3310-14

1/2 Bailer oil 3 hrs 3322.

600' oil & water in hole at 3355 1/2

Tests with Bailer;

1 1/2 Bailer water & 1/2 Bailer oil
first hour. 1 bailer water & 1/2
bailer oil second hour.

Lansing 2530
Chat 3264

Total Depth 3397

3264
1453
-1811