

State Geological Survey
**WELL COMPLETION REPORT AND
 DRILLER'S LOG**


API No. 15 — 075 — 20185
 County Number

S. 8 T. 22S R. 40 ^{NE} W

Loc. N/2 NW/4 SW/4

County Hamilton

640 Acres
 N



Elev.: Gr. 3,566

DF _____ KB 3,571

Operator
 Petro-Lewis Corporation

Address
 Box 2250, Denver, Colorado 80201

Well No. 1 Lease Name Alan

Footage Location
 660 feet from ~~XX~~ (S) line 1,980 feet from (E) ~~XXX~~ line

Principal Contractor D N B Drilling, Inc. Geologist James L. Donelson

Spud Date 2-26-77 Date Completed 3-1-77 Total Depth 2,765 P.B.T.D. 2,754

Directional Deviation None Oil and/or Gas Purchaser Kansas-Nebraska Pipeline

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 7/8"	8 5/8"	26#	335.30'	Class H	275	3% cc
Production	6 3/4"	4 1/2"	10.79#	2,754'	Class H	325	2%cc
					50-50 Pos Mix	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					2,706-18

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% HCL	2,706-18
Frac with 23,520 gal gelled water + 13,500# sd.	2,706-18

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator

DESTROYED TYPE OF COMPLETION: OIL, GAS, DRY HOLE, SWDW, ETC.:

Petro-Lewis Corporation

Well No. 1	Lease Name Alan
---------------	--------------------

S 8 T 22S R 40 ^K W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole				0 - 343
Shale & Shells				343 - 1030
Shale				1030 - 2034
Lime & Shale				2034 - 2605
Shale				2605 - 2714
Lime & Shlae				2714 - 2765 RTD

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Manager/Gas Marketing and Compliance
	Title
	11/29/79
	Date