

90115

1-30W MAP NO. K-50 SEC. 13-22S-41W  
STATE Kans COUNTY Hamilton LOC. App NE NE SW

OPER. Kansas Nebraska Nat Gas Co. - Hastings\* 200 FT/FR N LINE

WELL 1 FARM Z. Gould \*Nebr. 150 FT/FR E LINE

WOL Bradshaw ELEV. 3588 GR. 3593 DF 3595 KB

CONT. Chem Tech Drlg. GEOL. Doug Marden

CO. INT. 2750' Perm Test


F.R. 11-16-64 SPUD 12-3-64 COMP. 1-5-65

TD. 2736 FM. Winf PBTD.

Winf 2714 4 250A & Frac

Ga 3,156,000 Cfgpd & Some Water


8 5/8" @263 w/250 sx. 4 1/2" @2736 w/125 sx.



*Data Inc.*

(KB Log) No DST's, RTD 2736, Ran Log, 4 1/2" @2736  
Winf 2704 / 891 w/125 sx., Pf 4/2714 (Winf), 250A (15%),  
RTD 2736 / 859 Frac 8000 GA x 4000# sd x 200# hulls x  
10 tons CO-2, Rec part 1d, 5 hr Ga  
3,156,000 Cfgpd & some wtr, Winf 2714 - COMPLETED (12-29-64)

1-31W      MAP NO. K-50      SEC. 13-22S-41W  
 STATE Kans      COUNTY Hamilton      LOC App NE NE SW  
 OPER. Kansas-Nebraska Nat Gas Co. - Hastings\*      200      FT/FR N      LINE  
 WELL 1-D      FARM Z. Gould (SWD)      \*Nebr.      175      FT/FR E\*      LINE  
 POOL Bradshaw      ELEV. 3588      GR. 5-3593      DF 3595      KB  
 CONT. Chem Tech      GEOL. No Geol  
 CO. 1500' SWDW Test  
 INT. 11-16-64      SPUD 12-9-64      COMP. 1-5-65  
 F.R. 1540      FM. Glor      PBTD.



COMP. RECORD

SWDW

2 3/8" @1534 w/300 sx.

*Data Inc.*

(No tops)      RTD 1540 (Glor), 2 3/8" @1534 w/300 sx. Pf  
 20/1360-70 (Glor), 150A, SWDW (no tests avail) -  
COMPLETED (12-28-64)