


90120

9-205W REPLACEMENT COMPLETION
 MAP NO. _____ SEC. 21 TWP. 22S RGE. 41W
 STATE Kans COUNTY Hamilton 200' E of LOC. SE NW
 OPERATOR Hadsn Oil & Gas Co. FT. FROM _____ LINE _____
 WELL NO. 1 FARM NAME Sparr Unit FT. FROM _____ LINE _____
Bradshaw ELEV. 3579 GR 3585 E DF 3587 KB
 FR. 4/11/62 SPUD 4/24/62 COMP. 9/18/62
 CONT. Earl F. Wakefield Tools /GEOL. _____



NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Kri-Win</u>	<u>2622-2666</u>	<u>10</u>	<u>1000 A & Frac</u>
<u>Est Ga</u>			

a I. P. OIL/DIST. 0 WTR. 0 GAS 7500 M.C.F.P.D. _____ CHK. _____ HRS. 24
 b " " " " " " " "
 c " " SI Gas Well --- Temp. Comp. " "
 d _____

D & A ()

SIP# _____ FI TP # _____ FI CPH _____ SIBHP _____

GOR. _____ GR. _____ PBTD 2675 E TD 2699

SIZE	DEPTH	CASING W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>8 5/8" @</u>	<u>197</u>	<u>150</u>			
<u>4 1/2" @</u>	<u>2696</u>	<u>150</u>			

OPERATOR Hadson O & G WELL NO. 1 Sparr Unit ELEV. 3582 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

3000' Gas Test.

KB Tops & Datums

B/St Corral	2211	+1376
Herr	2577	+1010
Kri	2608	+ 979
Winf	2653	+ 934
RTD (Win)	2699	+ 888

RTD (Win) 2699. 4 1/2" @ 2696 w/150 sx. (Log) CO Perf 5/2666 (Win) NTN, 500 A, Ga 400 MCFGPD/17 hours., + load. Frac (20,000# sd x 17000 gal acid) Communicated. 1 hour BD. Ga 3500 MCFGPD, Set Plug 2634, Perf 5/2622 (Kri) NTN 500 A, Ga Est 4,000 MCFGPD/First 30", CO Plug @ 2634. CO 2675 Est PBTD, Est 7500 MCFGPD (Win & Kri) SI GAS WELL 9/13/62.

DATA, Inc. will report any further info on this test.

REPLACEMENT COMPLETION (10/30/62)

Additional information:

COMPLETED

