


90122

12-272W Map No. _____ REPL COMP
 OPER. KANSAS NEBRASKA NATURAL GAS CO., INC.
Hastings, Nebraska
#1 M. MILLER
 CONTRACTOR Paine Drilling, Inc.
 FIELD Bradshaw (Winf Gas)
 I.P. SIGW, Ga 4,140,000 CFGPD, Winf 2690



S-T-R 23-22S-41W
 SPOT App C W/2 E/2
 CO HAMILTON, Ks
 ELEV 3588 KB

(KB Logs:)

Glor	1319	/	2269
B/Glor	1382	/	2206
Cim Anh	2213	/	1375
B/" "	2232	/	1356
Red Cv	2232	/	1356
Herr	2600	/	989
Kri	2633	/	955
Winf	2628	/	960
LTD	2714	/	874
RTD	2714	/	874

DST #1 (Red Cv) 2220-2400, Op 80", GB, to WB/80", R 490'
 salty mud & 950' mdy SW, ISIP 789#/30", FP's 172#-646#,
 FSIP 789#/30", RTD 2714, Log, 5½" @2713'w/200 Sx.
 Pf 4/2690- (Winf), Frac 12,000 (3%) Gell A / 4000#
 sd / 200#, walnut hulls 176,000 CF - CO-2, 4 hr Ga 4,140,
 000 CFGPD, ISIP 445#, Winf 2690 - SIGW - COMPLETED on
12-20-65

REPLACEMENT COMPLETION for 1-13-66
Replaced with correct completion test, Was 41,140,000 - Is
4,140,000 CFGPD - Corrected on 1-11-66

CSO Log Log

Winfield 2678 + 910 + 4,140 mcf

Data Inc

MISCEL DATA	GEOLOGICAL	<u>Doug Marden</u>	ELEV	<u>3586 DF</u>	SPUD DATE	<u>10-21-65</u>
	FTG	<u>660' FWL & 100' FSL of NE/4</u>		<u>3581 GR</u>	DRIG COMP	
	SUPPT				FR by DATA	<u>10-4-65</u>
	CSG	<u>8" @259' w/200 Sx. 5" @2713' w/200 Sx.</u>			COMP by "	<u>12-22-65</u>