

State Geological Survey

WICHITA BRANCH KANSAS DRILLERS LOG

15-075-20141

API No. 15 — 075 — 20,141
County Number

Operator

Computer Petroleum Exploration Co.

Address

1600 Broadway, Denver, Colorado 80202

Well No.

1

Lease Name

Cheatum

Footage Location

1980 feet from (N) (X) line 2420 feet from (X) (W) line

Principal Contractor

DNB Drilling, Inc.

Geologist

R. Higginbottom

Spud Date

3-29-77

Total Depth

2668

P.B.T.D.

2648

Date Completed

4-16-77

Oil Purchaser


NA

S. 14 T. 22S R. 42 ^{NE} W

Loc. SE NW

County Hamilton

640 Acres
N



Locate well correctly

Elev.: Gr. 3581

DF KB 35868

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23	317	Class H	275	3% Ca Cl ₂
Production	7-7/8"	4-1/2	9.5	2663	Class H Pozmix	400 150	4 1/2% gel 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			8 holes (limited)		
Size	Setting depth	Packer set at			
2-3/8"	2619'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/500 gallons 15% HCl	2597-2608
Frac w/20830 gallons gelled 2% Kcl water + 13500# 20/40 sand	2597-2608

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
4-20-77	Flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	950	MCF	-	-
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Shut-in pending market			Upper Winfield		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 6044.

Operator

Computer Petroleum Exploration Co.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas well

Well No.

Lease Name

S 14 T 22S R 42 ^R_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Anhydrite
Sandstone
Sandstone
Sandstone2478
2510
2584

2166

Stone Corral
Herrington
Krider
Winfield2166 (Base)
2478
2510
2584

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Drilling & Production Superintendent

Title

4-25-77

Date

Dome
Attn: G.C. Bryant
Suite 1500 Colo St Bldg.
1600 Broadway
Denver, Colo 80202

14-22-42W

DRILLERS' LOG

CONFIDENTIAL

DOMO PETROLEUM CORPORATION
No. 1 Cheatum
SW NE, Sec. 14-22-42W
Hamilton County, Kansas

commenced: 3-29-77
completed: 4-1-77

Surface Casing: 309' of
8-5/8", cemented w/275 sx
Class H cement, 3%cc.
3-30-77

FORMATION

DEPTH

Surface Hole	0	-	317
Sand & Shale	317	-	785
Lime & Sand	785	-	1348
Lime, Shale & Sand	1348	-	1920
Shale	1920	-	2560
Lime & Shale	2560	-	2668 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 7th day of April, 1977.

Ella Priess

Ella Priess, Notary Public

