

90133

MAP NO. _____ OWWO _____ 3-9-61 _____ ELEV. 3510 DF
 STATE Kansas COUNTY Hamilton SEC. 25 Twp 22 S Rge 42 W
 OPERATOR Edwin L. Cox (Formerly Gulf Oil Corp) LOC. NW NW SE
 WELL NO. 1-25 FARM NAME Trussell FT. FROM _____ LINE _____
 POL WILDCAT FT. FROM _____ LINE _____
 FR. 11-18-60 SPUD 11-18-60 COMP. 3-5-61

CONT./GEOL. Holm Drilling tools - Woody Paul/Geol

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
 a Winfield 2537-58 56 750 Ac-F/60X50

b _____
 c _____
 d _____

a I. P. OIL/DIST. WTR. GAS 1.250 M.C.F.P.D. CHK. HRS. 6
 b " " " " " "
 c " " " " " "
 d _____

SIP# 430 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PSTD 2584 TD 5468

CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
 8-5/8" 926 600
 4 1/2" 2710 100

OPERATOR Edwin L. Cox WELL NO. 1-25 Trussell ELEV. 3510 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			New tops: Red Cave	2115	
			Upper Winfield	2537	
			Upper Ft. Riley	2605	
			Lower Ft. Riley	2638	
			Florence Flint	2710	
			Council Grove	2755	
			Heebner	3788	
			Toronto	3825	
			Lansing	3940	
			Morrow	4923	
			Ste. Genevieve	5253	
			St Louis	5408	

Old info: 8-5/8" @ 926 w/600 sx. OTD 3000. D & A 9-18-57.
 New info: MIR 11-18-60.
 DST # 1 (Morrow) 5048-63, op 1 hr, rec 610' SW, FP 137-274, SIP 1153/30 mins.
 DST # 2 (Morrow) 5172-5240, op 1 hr, gd blo, rec 390' MdyW, (S salty), FP 42-189, SIP 1139/30 mins.
 RTD 5468, logs (Sj). 4 1/2" @ 2710 w/100 sx (corr). MICT. CO to 2671

613155
P 16/2590-94, swb/NS. 500 Ac. Rec cl/NS. frac 5,000 wtr X
5,000 sd. rec ld/NS.

P 48/2546-58, 8/2537-39. Swb/NS. 750 Ac. Swb ld/NS. Frac
20,000 wtr X 20,000 sd. rec ld/SSG + 5-6 BXWPH. Set BP
@ 2584. g 100 MCF (NW), SIP 258#. Frac 40,000 Ac X
30,000 sd. Swb & flod ld w/ gas est 110 MCF. g est 120 MCF +
spray water. 24 hr g 2,200 MCF/slt spray wtr. 24 hr SIP
460#.. g 1,250 MCF, SIP 430#.

IP 6 hr BD g 1,250 MCF, SIP 430# from Winfield 2537-58.
Shut-In gas well.