


90132

11-200W MAP NO. 50 SEC. 13-22S-42W
 STATE Kansas COUNTY Hamilton LOC. C SW NE
 OPER. Texaco, Inc. Wichita, Kansas FT/FR _____ LINE _____
 WELL #1 FARM Blanche Smitherman FT/FR _____ LINE _____
 OL Bradshaw ELEV. 3593 GR. 3598 OF 3600 KB _____
 UNT. Chem Tech Drlg. GEOL. _____
 CO. _____
 INT. _____
 F.R. 9-9-63 SPUD 9-8-63 COMP. 11-19-63
 TD. 2674 FM. Winfield PBD. _____
 COMP RECORD blue shale D&A _____
 7" @244' w/150 Sx.
 4 1/2" @2640' w/370 Sx.



Data Inc.

KB Spl Tops:		KB Log Tops:	
Chase	2552 +1048	Win	2626
Winf	2629 + 971 ⁷⁶⁷⁶ _{OK}	Por	2636
Win por	2643 + 957	LTD	2666
RTD	2648 + 952		
DD TD	2674 + 926		

RTD 2648', No OH log, MICT, CO 2648' RTD, 4 way jet @1650' & Sq w/110 Sx. re=sq w/36 sx. Re-sq w/75 Sx. + 75 Sx. +125 Sx. + 50 Sx. CO 2648', RTD, No sho gas, DD to 2650', No sho gas, DD 2667', no sho gas, Ran GRN log, 2150-2665, DD 2674' TD,

SI 58 hrs. gas TSTM/2 hrs, perf. Win 28/2626-40, 500A in perms. & OH, no incr in gas, frac (10,000# sd x 15,000 gal 3% gelled A, \$ LW, w/GSG/10 hrs, \$ 151 BL & SW/10 hrs, Flo to BSW + 139,000 to 240,000 cfgpd/12 hrs. 13 hr. SIP 475#, \$ & flo 90 BSW + 200,000 cfgpd/10 hrs, PB 2638, \$ 10 BLW + 24 BSW/11 hrs. Ga. 170,000 cfgpd + 84 BSW/10 hrs, PB 2599', pfs @1650', still partially open, \$ 19 BSW/w/GSG/5 1/2 hrs. \$ 30 GMSW/9 hrs. CO 2674' TD \$ dn, \$ 24 BSW/3 hrs. flo 8 BSW/w/GSG/1 hr. Sqz OH & Perfs. 2626-40 w/150 Sx., Sqz @1650' w/125 Sx. CO 2640', Abra jet win @2632, FU 2 BW/w/no gas/11 hrs. Frac (7500# sd x 10,000 ga)\$ 40 BL & AW/4 hrs. w/NSG, \$ 95 BSW & LW/9 hrs. w/V sli SG last hr. Sqz 2632 w/150 Sx. CO 2640', abr jet 2 notches @2636', \$ dry/2 hrs. w/NSG, 500A(15%)Communicated w/abr jet @2636', \$ 25 BL & W w/NSG/NT. \$ 45 BAW & SW/8 hrs, w/SSG/ last hr., D&A 11-5-63

COMPLETED