

Phillips #1 Hitz

Ken
Stafford
7-22-12W
CSE NW

Eliv 1881

Tops by G.W. Spear

LKC 3334-1453, BAC 3554-1673, Chy V 3572 - 1041

5 3621-1740 A 3672-1791

casing 5 3672 RUST 3678 poor por some sat

Drilled in by W.E. McNeill

4/7/43 C.O. to bottom (3678) 12 gallon oil PH

4/8/43 Swab & bail down - Test 12 gal oil PH - no fill up
drill 3678-79 dol - some sat no incr oil - no sat

" 3679-80 10% dol, 50% c-m ang-rd sand - no inc
40% wash

" 3680-81 do

" 3681-83 m ang sd no inc

2 PM S.D. (wait on cable core barrel) Baker 24 hrs - 100' oil

4/9/43 Cable Core 3683-84 (3:35 PM - 4:10 PM) much oil mud

6 small biquets v den suc-mxk dol

(cuttings - some por & sat

5 PM 250' oil

Cored 3684-85 (7:10 PM - 7:40) no rec

8:45 PM 350' oil (cuttings 60% dol some por & sat 30% m 10% gns

Cored 3685-87 9:45 PM - 10:50 PM

rec few (4-5) sm per dol - few lgs cavern - bleed

cuttings: den dol - very little stain

11:30 PM 500' oil

4/10/43 Cored 3687-89 TD 12:10 AM - 1:00 AM

1:45 AM 1600' oil

rec 2' den dol with few vng &
fracture bleed of

cutting in fan por & sat - (probably fermaline)

TD 3689 - 1808 Swab

drop 1 man 335 lbs

1500 gal acid mcp 1000 + P975

198 bbls 1 1/2 hr

Pot 1234

depthograph (april 1943)