

MAYER
LEASE3
WELL NO.1
TEST NO.THOMAS H. ALLAN
COMPANYKANSAS
DISTRICT

LOCATION	14-22-8					Date	10-1-53
FIELD	Sterling Pool					Ticket No.	61109
COUNTY	Rice					HOWCO DISTRICT	Great Bend, Ks.
STATE	Kansas					Kind of Job	Open Hole
CONTRACTOR	Tom Allan					Price	\$215.00
MUD DATA		HOLE & TOOL DATA				Second Packer Assembly	-
Kind	Starch	Total Depth	3369'	Casing Perforations	Top Bottom	-	-
		Top Packer Depth	3338'	Bottom Packer Depth	-	-	-
Weight	10 lbs.-gal.	Casing or Hole Size	7 7/8"	Liner or Rathole Size	7 7/8"	Safety Joint	-
		Formation Tested	Mississippi Chat	Extra Folder Charge	-	-	-
Viscosity	35 Sec.	Size Drill Pipe	4 1/2" API FH	Size Drill Collars	5 3/4" x 120'	Jars	-
		Size Bottom Choke	1"	Size Surface Choke	1/2"		
Filter Loss	? c. c. Filter Cake 4/32 in.	Size Tool Valve		Size Pilot Valve			
BT. P.R.D. No.	292	Size Hook Wall Packer	-	Size Rings	No. Rings	-	
12 Hr. Clock No.	2055	Size D. E. Wall Packer	6 3/4"	No. Packers	1	Total	\$215.00
		PRD Device No.	1866	Blanked Off	Yes	Witnessed By	Tom Allan
Est. Gauge Depth Temp.	100 °F	Size & Length Anchor	4 1/2" x 31'			Tester	E. E. Folmsbee
Pressure Readings	Field	Office Corrected		REMARKS:			
Initial Hydro Mud Pressure		1762 p.s.i.	Opened tool at 12:55 P.M. with a strong blow, gas to surface				
Initial Flow Pres.	75	133 p.s.i.	in 18 minutes. Closed tool at 1:15 P.M. for 15 minutes. Started				
Tool Open	20 Minutes		out of hole at 1:30 P.M. Recovered 216' gas cut mud.				
Final Flow Pres.	190	171 p.s.i.					
Time Closed In	15 Minutes						
Closed In Pres.	1135	1163 p.s.i.					
Final Hydro Mud Pressure	1700 p.s.i.	Amount of Cushion	None	All depths measured from	Kelly Bushing	No. Folders Reproduced	5

PRESSURE

TIME

61109

Each Horizontal Line Equal to 1000 p.s.i.

