

SYLVIA

LEASE

2

WELL NO.

1

TEST NO.

THOMAS A. ALLAN

COMPANY

KANSAS

DISTRICT



OIL WELL CEMENTING CO.

Date 3-7-54

Ticket No. 89357

HOW CO DISTRICT Great Bend

Kind of Job Open Hole

Price \$215.00

Second Packer Assembly -

Safety Joint -

Extra Folder Charge -

Jars -

Total \$215.00

Witnessed By O. Goodwin

Tester L. D. Seibert

HOLE AND TOOL DATA

Total Depth 3062' Casing Perforations Top Bottom - -

Top Packer Depth 3045' Bottom Packer Depth -

Casing or Hole Size 7 7/8" Liner or Rathole Size -

Formation Tested Kansas City

Size Drill Pipe 4 1/2" Size Drill Collars 5 3/4" x 60'

Size Bottom Choke 5/8" Size Surface Choke 5/8"

Size Hook Wall Packer - Size Rings - No. Rings -

Size D. E. Wall Packer 6 3/4" No. Packers 1

Size & Length Anchor 4 1/2" x 17'

PRD Device No. 1866 Depth 3062' Blanked Off Yes

REMARKS: Tool opened with a weak blow that was dead in 21 minutes. Recovered 15' of drilling fluid.

12 Hr. Clock No. 3595

Pressure Readings Field Office Corrected

Initial Hydro Mud Pressure 1609 p.s.i.

Initial Flow Pres. 10 p.s.i.

Final Flow Pres. 10 p.s.i.

Closed in Pres. 523 p.s.i.

Final Hydro Mud Pressure 1609 p.s.i.

Amount of Cushion

None

All depths measured from

Kelly Bushing

No. Folders Reproduced

5

PRESSURE

TIME

89357

Each Horizontal Line Equal to 1000 p.s.i.

