

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.  
Addie Baughman No. 2

SEC. 1 T. 23 R. 10 W.  
SWc NE  
330' f S & 330' f W lines NE $\frac{1}{4}$

Total Depth. 3708  
Comm. 7-30-42 Comp. 9 -16-42  
Shot or Treated.  
Contractor. Harbar Drilling Co.  
Issued. 10-31-42

County Rono.

Rotary 3703  
Cable 3708



CASING.

85/8" 282' cemented.  
5 $\frac{1}{2}$ " 3696' cemented.

Elevation.

B.H.B. Ind.  
Production. Pot. 14,576 B.  
3000 B. Max. Flow.

Figures Indicate Bottom of Formations.

Bottom of cellar to surface level	6'2"
Surface level to Rig floor	3'
Rig floor to Top Rotary	2'4"
sand	150
red rock and shells	295
no record to	1447
sdv lime and shale	1550
sdv shale	1650
sdv lime	1790
lime	1895
sdv lime and shale	1920
lime and shale	1985
lime broken	2175
shale and lime shells	2290
lime and shale	2680
lime broken	2735
lime	3030
lime broken	3250
lime and shale	3305
lime	3365
lime and shale	3425
lime	3520
lime and shale	3530
lime	3550
lime and shale	3665
shale	3697
lime	3708
Total Depth.	

Top Viola 3703 Rig Floor.

Temporary Minimum test 9-17-42 made 46 bbls oil, no water swabbing natural.

Acidized with 500 gal. 9-23-42

State test. 9-25-42 with bottom hole bomb, made an indicated pot. 14,576 bbls for a 3000 bbls min. well flowing.