

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

CITIES SERVICE OIL CO.
Keesling No. 1.

SEC. 1 T. 23 R. 10 W.
SW₆ SW
330' N 330' E of SW cor.

Total Depth. 3745
Comm. 6-28-42 Comp. 7-19-42
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 9-5-42

County Reno.

CASING.

85/8" 152' cemented.
5 1/2" 3735' cemented.

Elevation.



B.H.P. Gauge

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. no wtr (Ind. Cap. 5645B)

surface sand	105
red bed and shale	330
gypsum and sand	395
red bed and shale	765
shale and shells	945
salt and shale	1165
shale and shells	1335
anhydrite and shale	1385
shy limo & shalo	1467
shale & lime	1720
sand	1745
broken lime	1873
shale and lime	2145
lime and shale	2428
lime	2460
lime and shale	2495
broken lime	2560
broken lime & shale	2754
lime	3005
limo and shalo	3173
shale and shells	3266
lime	3333
lime soft	3337
lime	3518
lime and shalo	3573
shale limo & chort	3613
lime	3650
shale & limo	3740
3740 Rot. T.D. 3739 SIM	
lime	3745

Total Depth.

Corr. Top Viola 3733
Penetration 12'

Loaded hole with 2500' water
before drilling in. cement set to
bottom rotary hole 3739.
good show oil 3741-45. no fillup.

500 gal July 25, 1942